ON THE EVALUATION OF AUTONOMOUS MOBILE ROBOTS

by

Gaurav Suhas Sukhatme

A Dissertation Presented to the
FACULTY OF THE GRADUATE SCHOOL
UNIVERSITY OF SOUTHERN CALIFORNIA
In Partial Fulfillment of the
Requirements for the Degree
DOCTOR OF PHILOSOPHY
(Computer Science)

May 1997

Copyright 1997 Gaurav Suhas Sukhatme

Acknowledgments

I thank Professor George Bekey for advising me and instructing me in the art of asking the right questions. He has given me a strong appreciation for the importance of empirical investigation which lies at the heart of science and engineering. It has been both a pleasure and a privilege to work with him.

The research reported here grew out of a project sponsored by the Jet Propulsion Labs as part of their Mars Rover Program. I thank Dr. Guillermo Rodriguez, the project manager, for all his help with the project and for serving on my dissertation committee. I also thank the other two members of my dissertation committee; Professors Ari Requicha and Stan Settles.

At USC I benefited greatly from the apprenticeship culture at the Robotics Lab where the senior graduate students play a major role in introducing new students to lab life. I thank Andy Fagg for being a great friend and a source of endless information on just about anything. I thank Tony Lewis for showing me that Computer Scientists could build hardware too.

Mike 'insert current middle-name here' McHenry has been a co-learner, co-sufferer and gossip companion through all the years since we took our introductory graduate classes at USC. For all that and more I am truly grateful. I thank Jim Montgomery for his eternal good humor and great company and for introducing me to some truly great beers. I'd also like to thank Joel Hoff and Jason Chu for their friendship. I thank Stergios Roumeliotis for reintroducing me to Kalman filtering and giving me a glimpse of the Mediterranean temperament. There are some

outstanding undergraduates who work in the lab and I've learned a lot by working with three in particular. Parag Batavia, whiz-kid extraordinaire and now a graduate student himself (Yes Parag it *still* takes an undergrad to do things right) - thanks for everything expecially an amazing airplane ride; Scott Cozy, designer, builder of robots and source of the most amazing bits of arcane knowledge; and Steve Goldberg, graphics and multimedia guru.

Immeasurable thanks to Scott Brizius for agreeing to work on the robots and in the sandbox and doing countless experiments with patience, skill and good humor.

For the first couple of years as a graduate student I shared an apartment with Sanjay Noronha; I couldn't ask for a better roommate. Thanks Sanjay - it was a lot of fun. Atul Konkar was another stellar apartment companion, I still remember all the late night discussion sessions on diverse topics.

I've been fortunate to have a great group of people helping me in the Computer Science office; Hilda Marti and Julieta Delapaz in particular who I'm sure I've driven crazy with my last minute reimbursement requests and other paperwork but who never lost their patience with me. I'd also like to thank Vilma Lorenzana, Amy Yiu, Steve Schrader, Paulina Baligod and Delsa Tan for all their help.

No amount of thanks are enough to acknowledge all the help and advice that I've got from Kusum Shori. Thanks for everything Kusum - you're the greatest.

My parents Suhas and Shobha Sukhatme have nurtured and supported me through all my life. They have also inspired me. I cannot thank them enough for all their love and encouragement. What measure of success I may achieve in life will always be largely due to them. Thanks also to my brother Jai who has always been supportive and continues to surprise me with his unique take on things. I also thank my wife's parents Balmohan and Nirmala Limaye, and my sister-in-law Aditi for all their love

and support. In addition I thank all my family members (too numerous to name individually, but no less important) for their love and encouragement.

The most significant event of my life was to get married to Kalyani. I've known her for nearly 8 years now but I continue to discover new and amazing things about her. She is my best friend and closest companion. With her love and support my years as a Ph.D. student have been very enjoyable. I thank her for everything.

Gaurav S. Sukhatme
Los Angeles, April 28, 1997

Contents

Acknowledgments ii

List Of Tables viii

List Of Figures ix

Abstract xii

1 Introduction 1
- 1.1 Motivation . . . 2
- 1.2 Background . . . 2
- 1.3 The Current Work . . . 5
- 1.4 Main Contributions . . . 7
- 1.5 Thesis Outline . . . 8

2 Previous Work 9
- 2.1 Multicriteria Evaluation . . . 9
- 2.2 Decision Analysis . . . 14
- 2.3 Development of Robots for Exploration . . . 16
  - 2.3.1 Wheeled Robots . . . 16
  - 2.3.2 Legged Robots . . . 19
- 2.4 Robot Evaluation . . . 21
  - 2.4.1 Static Evaluation Techniques . . . 21
  - 2.4.2 Dynamic Evaluation Techniques . . . 23
- 2.5 Robot Modeling . . . 24
  - 2.5.1 Kinematic Modeling . . . 25
  - 2.5.2 Dynamic Modeling . . . 26
- 2.6 Terrain Modeling . . . 28
- 2.7 Navigation and Path Planning . . . 30
- 2.8 Mathematical Ecology . . . 31
- 2.9 Summary of the Literature . . . 32

3 The Problem Formulation **34**
3.1 Designing an Evaluation Function 34
3.2 Classes of Robots 37
3.3 The Evaluation Jacobian 42
3.4 The Robot Mission 46
3.5 Three Hypotheses 48
3.6 The Problem Statement 51

4 The Experimental Setup and Protocol **53**
4.1 The Cost Functions τ and η 53
4.2 The Legged Robot: MENO 56
4.2.1 Robot Design 56
4.2.2 The Control System 58
4.3 The Wheeled Robots: Marscar and Arnold 69
4.4 The Navigation Algorithm 74
4.5 The Moore Distribution 77
4.6 The Sandbox Facility 78
4.7 The Experimental Protocol 80

5 The Dynamic Simulation Models **84**
5.1 MENO Simulation 84
5.1.1 Chassis Dynamics 84
5.1.2 Sensor and Actuator Models 85
5.2 Marscar Simulation 88
5.2.1 Chassis Dynamics 88
5.2.2 Sensor and Actuator Models 90
5.3 Interaction with the Environment 91
5.4 Implementation Specific Issues 93

6 Mobility Studies **96**
6.1 The Statistical Analysis 96
6.2 Mobility Trials in Mars Nominal 98
6.3 Clustering in Tradeoff Space 105
6.4 Sensitivity Studies - Robot Parameters 112
6.4.1 Robot Width 113
6.4.2 Robot Ground Clearance 114
6.4.3 Robot Velocity 116
6.5 Sensitivity Studies - Environment 118
6.6 Scalarization of the Metrics 118
6.7 Discussion and Summary 121

7 Scaling Studies **124**
7.1 The Smaller Wheeled System - Arnold 124
7.2 Comparison Data 126
7.3 Data Analysis 129
7.4 Summary 131

8 Diffusion Modeling **132**
8.1 Review of Diffusive Processes 132
8.2 Displacement vs. Time Model 134
8.3 Displacement vs. Energy Model 138
8.4 Summary 140

9 Conclusion **143**
9.1 Summary 143
9.2 Future Research 145

Bibliography **146**

List Of Tables

1.1 Missions and Critical Resources 2

4.1 MENO Mechanical Parameters 57
4.2 Arnold and Marscar Parameter Comparison 69

5.1 MENO model parameters 86
5.2 Marscar model parameters 89

6.1 The Figures of Merit for MENO and Marscar for Different Traverse Lengths 110
6.2 Elements of the Evaluation Jacobian for MENO and Marscar Calculated from Changes in Width 114
6.3 Elements of the Evaluation Jacobian for MENO and Marscar Calculated from Changes in Ground Clearance 116
6.4 Linear Scalarization of the Metrics 122

7.1 Arnold and Marscar Parameter Comparison 125
7.2 Predicted Values of τ and η Ratios Compared to the Measured Values 131

List Of Figures

1.1 A typical design cycle 3

2.1 Multicriteria Evaluation 11
2.2 Indifference Curves 13

3.1 The Wheel Module 38
3.2 The Leg Module 39
3.3 The Connection Modules 40
3.4 Tree Structures of Some Robots 41
3.5 Calculation of the Local Jacobian at a Particular Robot Configuration 44
3.6 Isochronal and Isoenergy Contours 47
3.7 A Slice Through C-space 49

4.1 A Schematic of $P(r > r_0)$ vs. Time 54
4.2 A Schematic Comparison of $P(r > r_0)$ vs. Time for Robots A and B . 55
4.3 MENO in a Simulated Martian Environment 58
4.4 A Plan View of the Straight Gait (forward is towards the top of the page, numbers indicate stability margin in cm) 59
4.5 A Plan View of the Turn Gait (forward is towards the top of the page, numbers indicate stability margin in cm) 60
4.6 The State Graph 61
4.7 MENO Parameters (plan view) 64
4.8 A Shift Maneuver (plan view) 65
4.9 A Trace of MENO Power Draw During Walking 66
4.10 MENO Pitch and Roll Regulation During Walking 67
4.11 Straight Gait Sequence ('forward' is to the right of the page) 68
4.12 The MENO Control System Architecture 70
4.13 Marscar in a Simulated Martian Environment 71
4.14 The Control Architecture for the Wheeled Robots 73
4.15 The Navigation Algorithm 74
4.16 The Detour Strategy (plan view): **a** is preferred over **b** 76
4.17 Navigation Accuracy for MENO and Marscar 76
4.18 A Typical Traverse for MENO and Marscar 77
4.19 The Exponential Moore Distribution 78

4.20 The Marsbox with MENO and Marscar 79
4.21 The Experimental Protocol for the Isochronal Measurements 81
4.22 The Experimental Protocol for the Isoenergy Measurements 82

5.1 The MENO simulated model (only the chassis and one leg is shown) . 85
5.2 The Marscar simulated model. For convenience the angles θ_2, ϕ_2, θ_3 and ϕ_3 are not shown 88
5.3 A plan view of the simulated wheeled robot Marscar 90
5.4 Ground Friction as a Function of Rotational Speed 92
5.5 Axle Friction as a Function of Rotational Speed 93
5.6 a. Contact between a MENO foot and a rock and b. Contact between Marscar and a rock 94
5.7 A flow diagram of the dynamic simulation 95

6.1 Average Displacement vs. Time for Marscar in Mars Nominal Terrain 100
6.2 Average Displacement vs. Energy for Marscar in Mars Nominal Terrain 101
6.3 Average Displacement vs. Time for MENO in Mars Nominal Terrain 103
6.4 Average Displacement vs. Energy for MENO in Mars Nominal Terrain 104
6.5 Marscar - Probability of reaching threshold displacements vs. time in Mars nominal terrain 106
6.6 Marscar - Probability of reaching threshold displacements vs. energy in Mars nominal terrain 107
6.7 MENO - Probability of reaching threshold displacements vs. time in Mars nominal terrain 108
6.8 MENO - Probability of reaching threshold displacements vs. energy in Mars nominal terrain 109
6.9 A Comparison of MENO and Marscar in Mars Nominal terrain for Different values of k 111
6.10 A Comparison of MENO and Marscar in Mars Nominal terrain for $k = 5$ as a Function of Time Elapsed 112
6.11 A Comparison of MENO and Marscar in Mars Nominal terrain for $k = 5$ as a Function of Energy Consumed 113
6.12 Effect of width change on MENO and Marscar in Mars Nominal terrain for different values of k 115
6.13 Effect of change in ground clearance on MENO and Marscar in Mars Nominal for different values of k 117
6.14 Effect of increased speed on MENO mobility in Mars Nominal terrain for different values of k 119
6.15 MENO and Marscar mobility in Viking II (cluttered) terrain for different values of k 120

7.1 Ackerman Steering on Marscar and Arnold 125
7.2 Marscar and Arnold in Mars Nominal terrain for different values of k 127

7.3 Marscar and Arnold in Viking II terrain for different values of k . . . 128

8.1 Average Displacement of Marscar as a Function of Time Fitted to a Diffusive Model . . . 136
8.2 Average Displacement of MENO as a Function of Time Fitted to a Diffusive Model . . . 136
8.3 Average Displacement of Marscar as a Function of Time Fitted to a Diffusive Model with Drift . . . 138
8.4 Average Displacement of MENO as a Function of Time Fitted to a Diffusive Model with Drift . . . 139
8.5 Average Displacement of Marscar as a Function of Energy Fitted to a Diffusive Model . . . 139
8.6 Average Displacement of MENO as a Function of Energy Fitted to a Diffusive Model . . . 140
8.7 Average Displacement of Marscar as a Function of Energy Fitted to a Diffusive Model with Drift . . . 141
8.8 Average Displacement of MENO as a Function of Energy Fitted to a Diffusive Model with Drift . . . 141

Abstract

In this dissertation we pose the problem of evaluating robot performance in a multiple criteria framework. Specifically, we propose a new evaluation methodology for mobile robots navigating in terrain cluttered with obstacles. The technique relies on a combination of multiple statistical criteria. We present a comparative performance analysis of three physical robots to which the evaluation functions were applied. One of the systems constructed for the experiments is a novel quadruped robot; the other two are four wheeled systems. Physics based dynamic simulations of the systems were written, validated, and subjected to the same evaluation functions as the real robots. Nearly 1000 runs of the simulated traverses were performed to obtain a high degree of confidence. Statistics of these runs show that the simulations were good representations of the actual systems. Further, we present sensitivity studies that measure the effects of small parameter changes on the overall system performance. The simulations were also used to study the effects of scale on the mobility metrics. For the navigation task under study we conclude that the robot width and ground clearance are crucial parameters that affect the mobility performance significantly. We also show that the proposed metrics partition the evaluation space in a meaningful way. A diffusion based model was built which predicts robot mobility successfully. The dissertation concludes with a discussion of alternative metrics, alternative techniques to scalarize what is inherently a multidimensional evaluation problem and other directions for future research.

Chapter 1

Introduction

The central theme of this thesis is to provide a prescription for quantifying mobile robot performance. At the present time standardized techniques for such quantification do not exist. In Robotics, as in other engineering disciplines the demand to quantify performance stems from the need to refine existing designs. Performance quantification also contributes to the development of the discipline as a science since it allows design to proceed based on a set of principles instead of an ad hoc manner.

To keep the problem tractable we focus on a particular class of mobile robots and a particular operating envelope as examples in this study. The techniques developed here however are applicable to other classes of robots built for the operating envelope under consideration. Techniques similar to the ones developed in this study can be applied to other operating conditions with suitable modifications.

The main idea behind the proposed approach to performance evaluation is to use the **task** or **mission goal** as a starting point for performance metrics. Since performance is typically dependent on critical, limited resources the next step is to identify the most important of these resources and incorporate them in the metrics as constraints. Since the critical resources are usually multiple the evaluation problem is a multidimensional one. The (vector) output of the multiple evaluation functions is finally scalarized in some meaningful way. In addition the proposed approach addresses a domain where information about the environment is scarce.

The nature of the known information is statistical. The metrics proposed here are thus Monte-Carlo methods to measure performance probabilistically.

1.1 Motivation

As motivation we mention that domains where the environment is unknown (or at best statistically characterized) and resources are critical are not as scarce as they may seem at first sight. Examples are given in Table 1.1.

The idea behind the approach proposed in this work has been successfully applied in other disciplines where the design problem can be cast in terms of a set of desired goals and a set of limited resources. The original formulation of the problem in these terms is due to Pareto (Pareto 1971) whose work in multiple criteria evaluation we examine in the next chapter. Complex system evaluation often takes this form in other contexts such as economics, public policy, chemical plant design and so on. It has been applied with great success to these diverse problems. As robotics technology matures it is important to employ such well understood techniques to robot design and to examine their efficacy.

Table 1.1: Missions and Critical Resources

Mission	*Critical Resource(s)*
Search and rescue in urban environments	Time, Size/Space
Hazardous waste disposal	Time
Planetary exploration	Time, Energy, Computational Power

1.2 Background

Before giving a synopsis of the current work and the major results we present a general view of the research area in which this work is situated. The current work is



Figure 1.1: A typical design cycle

an instance of the general problem of evaluating complex dynamical systems. Evaluating systems that are domain specific is an engineering task tied closely to the problem of design optimization.

Figure 1.1 shows a typical design cycle. An abstraction of the task/mission enables the designer to construct a model. The model may be a computer simulation, a physical scale model or a set of differential equations that can be solved numerically or (rarely) in closed form. In some industries all three are employed before a full size machine is built (an example is the aircraft industry). The simulation and the equations are parameterized so that one can generate a large number of designs and thus explore the design space. An evaluation function (or a set of functions) is then used to decide which design is best. A satisfactory state of affairs is reached when at least one final design (the "best" design) is found using the above method. We will say then that this final design represents a solution to the design problem and the design cycle is a method to solve the design problem. An interesting question is "How does one arrive at a satisfactory evaluation function ?". The **evaluation problem** is to build the box labeled evaluation function in Figure 1.1. The problems of design and evaluation are thus closely related.

For physical systems the equations describing the behavior of the system are usually nonlinear. For example the system may have a set of m variables of interest $\mathbf{x} = [\mathbf{x_1}, \mathbf{x_2}, \ldots \mathbf{x_m}]$. In general, all elements of $\mathbf{x}$ may not be observable and some

subset (or nonlinear combination of them) denoted by the $n \times 1$ vector $\mathbf{y}$, where $n \leq m$, is observable. $\mathbf{y}$ and $\mathbf{x}$ are functions of time t. The set of equations that describe the system is given by:

$$\dot{\mathbf{x}} = \mathbf{g}(\mathbf{x}, \mathbf{p}, \mathbf{q}, \mathbf{t}, \mathbf{w}) \tag{1.1}$$

$\mathbf{w}$ is a noise process which lumps all system and environment noise together. For purposes of analytical solution it is often idealized to be perfect white noise. The k design parameters are denoted by the $k \times 1$ vector $\mathbf{p}$. The environment is parameterized by the $l \times 1$ vector $\mathbf{q}$. An evaluation methodology is a set of r functions $\mathcal{F} = \{f_1, f_2, \ldots f_r\}$ that maps a particular choice of system design and environment (given by specifying $\mathbf{x}$, $\mathbf{y}$, $\mathbf{p}$ and $\mathbf{q}$) to a $r-$ dimensional evaluation vector $\mathbf{v}$. The next step is to impose an order on the set of all such ($r-$ dimensional) evaluation vectors $\mathbf{v}$ in order to compare any two of them.

$$\mathcal{F} = \{f_1, f_2, \ldots f_r\} : \{\mathbf{x}, \mathbf{y}, \mathbf{p}, \mathbf{q}\} \rightarrow \mathbf{v} \tag{1.2}$$

In summary, design optimization involves

1. Selecting a set of design variables to describe the design alternatives. (This set includes variables and parameters)

2. The selection of an evaluation (objective) function which is expressed in terms of the design variables and design parameters.

3. The constraints that any design candidate has to satisfy.

4. The selection of the final design from the set of candidate designs.

This work focuses on step 2 in the above scheme. The chosen context for this work is the field of mobile robot design within a specific mission envelope.

1.3 The Current Work

In the current work the example mission chosen is an autonomous traverse through rocky terrain by a mobile robot. Such a mission will be executed by a six wheeled mobile robot called Sojourner as part of the Mars Pathfinder mission launched by NASA in December 1996 and scheduled to arrive on Mars in July 1997 (Matthies, Gat, Harrison, Wilcox, Volpe & Litwin 1995). Little is known about the terrain on Mars and the question of a suitable design for such an exploration mission is an unresolved one. Missions such as this one are expensive and rare. Clearly a systematic design methodology would improve both cost-effectiveness and the chances of success; both of which are highly desirable. In the present work we propose two evaluation metrics for this mission based on the two critical resources available to the robot namely time and energy. The metrics proposed are then used to evaluate two robot designs which differ widely (one has legs and the other is a wheeled system). This scenario was chosen because it satisfies the following criteria which contribute to the difficulty of the evaluation problem.

1. There are (due to technical constraints) tight upper bounds on the size, power requirements and computation capability of the systems that populate the design space.

2. The mission environment is unseen - no map exists of the vicinity. The only information about the environment is statistical in nature extrapolated from earlier data taken elsewhere. We return to this issue in Chapter 3.

3. The design space that can produce solutions to the problem is extremely large i.e. there are many candidate designs. Examples are legged vehicles, wheeled vehicles, tracked vehicles, hybrids etc.

4. The formal notion of a mission is hard to capture.

Evaluation of complex systems is difficult because items 1-4 above are a common occurrence in many realistic contexts. We have, thus, reason to believe that the example chosen in this study is representative of a set of challenges common to diverse complex engineered systems.

Having built and evaluated the two example robot designs we exhibit validated, dynamic simulation models of both of them. The models are subjected to the same evaluation methodology as the physical systems and it is shown that their evaluations are similar to their physical counterparts. Thus armed we use the simulations to perform parameter sensitivity studies in the neighborhoods of the proposed designs. This is useful in local design optimization.

A third component of this work is a study of effects of scale. Complex systems such as the ones under study have nonlinear dynamics which make scale effects (such as size dependence) difficult to predict analytically. Physical models and validated simulation models can be used to study scaling. We study the case of a smaller wheeled system in the same environment as the original wheeled system and describe the effects of size change on the performance metrics. The same study is also done in simulation.

The last component of the current work is a characterization of the problem of robot navigation in rocky terrain in geometric terms. It is shown that the motion of a mobile robot navigating reactively in such terrain can be modeled fairly well as a diffusive process. This result is a useful beginning towards modeling the effects of navigation algorithms in statistical terms.

1.4 Main Contributions

The main contributions of this work may be viewed in two parts; the first part is the completion of a set of research goals; the second part is a set of results due to the application of the proposed evaluation functions and is to be viewed as empirical support for the usefulness of the proposed techniques.

Research contributions

1. A set of functions denoted $\mathcal{F} = \{\tau, \eta\}$ has been found which allow classification of the robot design space. τ is a measure of the time efficiency of a design and η is a measure of its energy efficiency.

2. The proposed functions τ and η have been evaluated on select members of the design space; both in experiment and simulation.

3. A technique using local linearization has been developed to extrapolate to other (untested) members of the design space.

4. A diffusion based model of the reactive navigation strategy employed in the experimental work is exhibited.

Empirical findings pertinent to the systems studied as examples.

1. A methodology for evaluating the comparative effectiveness of Mars locomotion vehicles has been developed

   (a) The methodology has been applied to both legged and wheeled robots in our lab

   (b) The methodology can be applied to a wide class of other vehicles (e.g. tracked, leg/wheel hybrid etc.)

2. For the class of vehicles considered in this study, on a rocky Mars-like terrain, wheeled vehicles offer advantages in speed and energy consumption

3. Amongst robots that use obstacle avoidance as their main strategy smaller robots have increased mobility in cluttered terrain

4. Sensitivity studies show that in the neighborhood of the proposed designs the mobility of the wheeled robot is significantly affected by small changes in width and ground clearance. The legged system is less sensitive to changes in these parameters.

1.5 Thesis Outline

A chapter by chapter outline of the rest of this dissertation is as follows; in Chapter 2 we survey the relevant literature; in Chapter 3 we present a formal statement of the problem under study; in Chapter 4 a description of the robots that were built as part of the study is given as is a description of the experimental protocol used; in Chapter 5 we describe the dynamic simulations of the robots that were constructed; in Chapter 6 the main results of the evaluation studies are discussed; in Chapter 7 the experiments that measure scale effects are discussed; in Chapter 8 the motion of the robots is modeled as a diffusive process and finally in the last chapter we conclude with a summary of the major contributions of this work and a short discussion of possible directions of future research.

Chapter 2

Previous Work

As noted in the previous chapter, this work is interdisciplinary. In this Chapter we review pertinent literature from diverse fields namely, multicriteria evaluation, optimization theory, decision theory, mobile robotics, robot modeling, terrain modeling, navigation and path planning and robot evaluation techniques all of which are pertinent to the work described here.

Multicriteria evaluation, optimization theory and decision analysis deal with the science of evaluating complex systems and (design) decision making in the face of uncertainty. Robot and terrain modeling, navigation, path planning and robot evaluation techniques are subjects from robotics that influence this work.

2.1 Multicriteria Evaluation

An intuitively appealing way to evaluate a complex system is to break it into parts and assign each part some "weight" or "importance". The system is decomposed into parts so that each part has a simple structure and is easy to evaluate [1]. The composite system is then assigned a figure of merit using a weighted combination (possibly linear) of the parts. Further thought reveals that there is an assumption behind this technique which is often fallacious. The decomposition which is

[1] In this intuitive argument assigning a figure of merit to each part is called "evaluating" it.

described above is not possible for many complex systems. These systems may be viewed as an interaction of several subsystems which are *strongly coupled* to each other and are *not* independent. A functional decomposition for piecemeal evaluation may not be possible.

The natural extension is therefore to model coupling between subsystems and continue using the above weighting technique. The result is a branch of systems theory called multicriteria evaluation. The price paid for modeling coupling between various subsystems is seen in the domain of the cost function which was a set of scalars (figure of merit) and must now be treated as a set of vectors instead. This is illustrated below.

Simply put, multicriteria evaluation is the branch of research that deals with non-scalar optimization i.e. the range of the evaluation function is a set of vectors. To explain multicriteria evaluation we use a simple linear example.

Consider a problem in linear programming (LP) expressed in canonical form.

$$Maximize\ z = \mathbf{c}^T\mathbf{x}\ \ such\ that\ \ \mathbf{A}\mathbf{x} \leq \mathbf{b}\ \ and\ \ \mathbf{x} \geq 0 \tag{2.1}$$

where z is a scalar, the $n \times 1$ vector $\mathbf{x}$ is the set of n decision variables, $\mathbf{c}$ is a $n \times 1$ vector of costs or weights and $\mathbf{A}$ is the $m \times n$ matrix which denotes the set of m constraints. The first part of equation 2.1 is the cost or evaluation function which we wish to maximize. The second part is the set of (linear) constraints that $\mathbf{x}$ must satisfy.

It can be shown (Helmke & Moore 1994) that for a convex set of constraints there always exists a unique solution for a LP problem. A standard solution technique such as the Simplex method (Dantzig 1963) or an interior point method (Karmarkar 1984) may be applied to solve the problem.



Figure 2.1: Multicriteria Evaluation

By contrast, a multicriteria LP problem is given by the following canonical form.

$$Max\ \mathbf{z} = \mathbf{C}^T\mathbf{x}\ \ such\ that\ \ \mathbf{A}\mathbf{x} \leq \mathbf{b}\ \ and\ \ \mathbf{x} \geq 0 \tag{2.2}$$

The second part (i.e. the constraints) of both equations 2.2 and 2.1 is the same whereas the output of the cost function is a vector in equation 2.2 as opposed to 2.1 where it is a scalar. As before $\mathbf{x}$ is the $n \times 1$ vector of decision variables and $\mathbf{A}$ is the $m \times n$ matrix which denotes the set of m constraints. The set of k costs $\mathbf{C}$ is a $m \times k$ matrix. The output is thus a $k \times 1$ vector $\mathbf{z}$.

This presents a problem since it is not clear how one maximizes a vector in a "natural" sense (like a scalar). The above example is taken from linear programming but in general neither the cost function nor the constraints have to be linear. One cannot maximize the cost directly in a multicriteria problem (one ends up maximizing $\| \mathbf{z} \|$ for instance) but one can still make some progress towards a solution. Consider a two dimensional problem as shown in figure 2.1. z_1 and z_2 are the two components of the cost function. The set of constraints define the feasible region. The rest of the space is called the infeasible region and the boundary between them

is called the transformation curve.

The concept of an optimal solution (i.e. that which maximizes $\mathbf{z}$) is now replaced by the concept of a noninferior solution. A solution $\mathbf{x}$ is noninferior if there is some solution $\mathbf{w}$ such that

$$z_1(\mathbf{x}) \geq z_1(\mathbf{w}) \; ; \quad z_2(\mathbf{x}) \geq z_2(\mathbf{w}) \tag{2.3}$$

where at least one of the above inequalities holds strictly. It turns out that all noninferior solutions that satisfy equation 2.3 are a subset of the transformation curve in Figure 2.1. Research in multicriteria evaluation has focussed largely on generating the noninferior set and leaving the final choice of solution to a human designer/specialist. The notion of the noninferior set was introduced by Pareto (Pareto 1971) in the context of a multitude of objectives in economics. The non-inferior set is called the set of Pareto-optimal solutions. The concept of the noninferior set is also the same as the notion of a satisfycing solution found in Artificial Intelligence literature.

Literature on methods to find the noninferior set is extensive (Cohon & Marks 1974) and (Eschenauer, Koski & Osyczka 1990) are examples. There are two main techniques to find the non-inferior set. Both rely on transforming the objective function into a scalar function (*scalarization*). The first is a weighting technique. Consider Equation 2.2 and reformulate it as follows:

$$\begin{aligned} Maximize \;\; \Sigma\lambda_i z_i = z_n + \lambda_{n-1} z_{n-1} + \ldots + \lambda_1 z_1 \\ Where \;\; \mathbf{z} = \mathbf{C}^T\mathbf{x} \\ Such\ that \;\; \mathbf{A}\mathbf{x} \leq \mathbf{b} \;\; and \;\; \mathbf{x} \geq 0 \end{aligned} \tag{2.4}$$

where the objective function is now a scalar . One of the λ_i is chosen to be unity and all other objectives are weighted by the $\lambda's$. If the non-inferior set is



Figure 2.2: Indifference Curves

strictly convex one can generate it by varying the $\lambda's$. If however the non-inferior set is non-convex then the weighting technique fails to generate the entire set. To tackle this case Facet (Facet 1970) introduced the constraint method. Consider the 2 dimensional case of 2.2 and transform the problem as follows:

$$\begin{aligned} Max \quad & z_2 \\ Where \quad & \mathbf{z} = \mathbf{C}^T\mathbf{x} \\ Such\ that \quad & \mathbf{Ax} \leq \mathbf{b} \quad and \quad \mathbf{x} \geq 0 \ and \ z_1 \geq B_1 \end{aligned} \tag{2.5}$$

The objective function is thus scalarized by including all but one of the objectives in the constraints. B_1 is now set to some lower bound and increased incrementally until the solution becomes infeasible. At each value of B_1 the above scalarized problem is solved giving a point in the non-inferior set of the original problem in 2.2.

Once the non-inferior set has been generated a solution is picked from it based upon an *indifference* measure. An indifference measure refers to the quantity of one of the objectives that one is willing to trade off for the others. In a two-objective

problem one may have linear trade offs such as $z_1 + z_2 = \ constant$ or quadratic tradeoffs such as $z_1 z_2 = \ constant$.

The solution to the problem is the intersection of the indifference curve and the non-inferior set as shown in Figure 2.2. There are several issues that multicriteria evaluation techniques do not address or solve. Some of them are as follows:

1. The scalarization used in solving the problem is arbitrary.
2. There is an assumption that an underlying indifference measure can be readily formulated.
3. The representation forces one to simplify - i.e. if one wants to use analytical techniques than one has to assume simplified (usually linear) constraints.
4. The framework does not incorporate uncertainty or noise.

Multicriteria evaluation has been applied to several fields with great success from urban planning to public policy to shop layout. A single criterion analysis has been adapted for use in robot evaluation (Lietzau 1993) as we discuss later in this chapter. In this work we introduce two cost functions and propose an indifference measure on the space spanned by them. To our knowledge this is the first application of multiple criteria methods to mobile robot evaluation.

It may also be noted here that other multicriteria evaluation techniques exist (Eschenauer et al. 1990) but they variants of the above theme. To some extent, the science of decision analysis addresses the issue of uncertainty in decision making. This is the topic of the next section.

2.2 Decision Analysis

Decision analysis is the science of making a choice from multiple options in the face of incomplete (possibly incorrect) information. Furthermore the choices one makes

may affect other decisions further down the line. Examples of problems in decision theory range from game theory, economics, engineering design etc. A brief review of the principles of decision theory is given here since the problem of robot evaluation is closely related to the the problem of robot design as mentioned in Chapter One. Robot design is not the focus of this thesis however, and this section merely skims the surface of the existing literature.

To quote Chankong (Chankong & Haimes 1983), "Decision analysis is a formal procedure to aid the decision maker in solving certain types of decision problems where

1. The set of alternative actions is finite and pre-specified
2. Only one attribute or objective function is to be optimized and
3. The environment is uncertain

Once the (design) decision problem has been defined the analysis uses probability theory and an estimate of outcome value for each decision. Based upon maximization of expected utility (Raiffa 1968) , (Keeney & Raiffa 1993) design decisions can then be made.

While decision analysis has a framework to deal with uncertainty the problem of robot design does not easily fit the three criteria enumerated above. One does not know (even probabilistically) the effects of making a design decision (say about the kinematic configuration of the robot) on the performance of the robot. Part of the reason for this is identically the theme of this thesis i.e. how does one measure the performance of a mobile robot ?

2.3 Development of Robots for Exploration

In recent years with the advent of cheap sensors and fast computers there has been an explosion in the development of mobile robots. Most work in mobile robotics tends to be focused on indoor environments. However there is a substantial amount of research that deals with problems in building robots for outdoor exploration in rugged terrain. As mentioned before , we restrict ourselves to land-based exploration in this study. In this section we review some of the systems built for land-based robotic exploration. We will treat wheeled systems separately from legged systems.

2.3.1 Wheeled Robots

At the Jet Propulsion Labs a family of robots has been developed for planetary exploration. The current version of their wheeled testbed (Gat, Desai, Ivlev, Loch & Miller 1994) called Rocky IV has been extensively tested for planetary exploration[2] Rocky IV is a 6 wheeled robot with an innovative suspension called a rocker-bogey. The suspension partially decouples the terrain from the sensor platform so that when a terrain feature causes the two-rocker arm mechanisms to pitch the sensor platform experiences only their average pitch thereby providing the stability that the sensors need. The robot is equipped with four infrared proximity sensors, a contact sensor, pitch and roll inclinometers, a compass and an encoder on each wheel. All six wheels are independently steerable and actuated. In addition to these sensors the robot is equipped with instruments such as a visible light spectrometer, a chipping tool and a small color video camera.

Rocky IV is equipped with a behavior based controller (Gat, Behar, Desai, Ivlev, Loch & Miller 1994), (Gat, Desai, Ivlev, Loch & Miller 1994) which is inspired by the behavior based control proposed by Brooks in (Brooks 1986). The basic insight

[2]The space qualified version of Rocky IV called Sojourner is on its way to Mars as this Thesis is being written. Its planned arrival on Mars is July 4, 1997.

is that the control problem is decomposed by task rather than function. There are special purpose modules for each task that the robot has to perform such as obstacle avoidance, goal seeking and so on.

The basic navigation strategy that Rocky uses is as follows. Given a heading it turn towards it. If both front infrared sensors detect an obstacle then the robot turns approximately 45 deg and tries to move forward. If a single forward infrared sensor is activated then the robot turns away from that direction. If the front bumper is activated then the robot backs up and turns approximately 45 deg and goes forward. This simple reactive strategy is found to work quite well. It is parameterized by the turn angles and the backup distance both of which are preset in Rocky.

The current incarnation of the Rocky series which has been deployed in the field and extensively tested is called Rocky VII (Volpe, Balaram, Ohm & Ivlev 1996). It also uses a rocker-bogey suspension but is slightly lighter than Rocky IV. The main difference between the two in terms of mechanics is that Rocky VII uses two-wheel steering instead of four wheel steering. Also two wheels on either side of Rocky VII can be electrically coupled thus reducing the degrees of freedom (DOF) required for locomotion even further to six. The 4 DOF saved are used to drive an onboard manipulator which has a 2 DOF shoulder and a 2 DOF scoop mechanism for soil sampling.

Over the past decade researchers at MIT have developed a family of robots that can navigate using simple sensors. Mobility of these (wheeled) robots for natural terrain has not been reported. Since most of these systems were not designed to move outdoors we will not report on them in detail here. In the next section we discuss some of the MIT legged robots which have walked on uneven terrain.

Research at CMU (Pomerleau 1992) has produced a system which controls a four wheeled vehicle, a modified van called Navlab, during travel on paved roads as well

as off the road traverses. Navlab was initially controlled by ALVINN, a backpropagation neural network that learned by watching a human driver. Since then Navlab has been adapted for off the road applications (Langer, Rosenblatt & Hebert 1994). A similar autonomous road vehicle was built in Germany by Dickmanns (Dickmanns & Zapp 1987).

Under the auspices of the CNES (French Space Agency), a program called VAP (Autonomous Planetary Rover) has been underway at several French institutions for nearly five years. The main body of work that has been developed here is in modeling the dynamic behavior of a six-wheeled rover in simulation (Jimenez, Luciani & Laugier 1993), (Cherif, Laugier, Milesi-Bellier & Faverjon 1994), (Cherif & Laugier 1994) and (Milesi-Bellier, Laugier & Faverjon 1993)

In (Jimenez et al. 1993) the authors present a physical model of a six-wheeled robot for planetary exploration and show its application by executing a partially specified motion on a given terrain. The work is further extended in (Cherif et al. 1994) to include the effects of slip on natural terrain.

The work by Cherif et al. (Cherif et al. 1994), (Cherif & Laugier 1994) builds physical models of the terrain as an interacting set of spherical particles. The robot terrain interaction is modeled as a spring damper mechanism. Their system is able to accept an elevation map of the terrain and instantiate a physical model for it. Based on the physical model the system is able to classify the configuration of the robot on the terrain as "stable" or "unstable". The motion planner accepts a start configuration and a goal configuration of the robot as input and plans a sequence of "stable" configurations between them. The authors do not report whether the physical model was instantiated using a real robot. It is also unclear whether their results have been compared to the performance of a real robot. Nevertheless their physical system modeling is state of the art and is rigorously done without undue simplification. We discuss further details of their work in the sections on robot and

terrain modeling.

2.3.2 Legged Robots

Research at CMU has produced Ambler (Krotkov & Hoffman 1994), (Simmons 1994) and Dante - legged vehicles built for exploring in extremely rugged and demanding conditions. These are perhaps the most sophisticated walkers built to date and also the most successful in terms of field performance.

Ambler is a walking robot designed to traverse extreme terrain. It has six legs which are arranged three on a side in two stacks. Each leg is a RPP[3] configuration with the first two links in the horizontal plane and the third link in the vertical plane. This decoupling between the horizontal and vertical planes eliminates gravity loading along two of the three joint axes in each leg. The inverse kinematics and hence the control are also simplified. The robot is equipped with a force/torque sensor on each foot and a scanning laser rangefinder which measures range and reflectance. The walking system consists of many distributed modules which communicate by message passing. Ambler has been demonstrated in extended trial periods in rugged outdoor terrain.

Dante is an eight legged frame walker composed of two four legged frames which slide with respect to each other. Typically one frame is always in contact with the ground. Each leg is a pantograph mechanism. Dante is designed to descend steep cliffs in hazardous conditions using a tether to support its weight. It has been successfully demonstrated in Antarctica and Alaska. It uses two inclinometers to sense body attitude and several cameras. It also uses a scanning laser range finder to do terrain mapping.

[3]RPP stands for rotational, rotational, prismatic - the types of joints and their order from inner to outer on a particular leg

Researchers at the Ohio State University developed the Adaptive Suspension Vehicle (ASV) for exploration of outdoor terrain (Song & Waldron 1989). The ASV had a human operator and was capable of carrying a 500 lb. payload. The ASV has been demonstrated in outdoor environments in human controlled and fully autonomous mode. The main research thrusts in the ASV development effort were gait analysis for level and sloped terrain, gaits for obstacle crossing, control and force algorithms and design of leg geometry. Recent advances in sensor technology and microelectronics have rendered much of the electronics on board obsolete but the control and force algorithms for walking on rugged terrains are still used.

An extensive body of work by Hirose and colleagues (Hirose 1984), (Hirose, Kikuchi & Umetani 1986) and (Hirose & Kunieda 1991) has led to the development of extraordinary quadruped walkers. Examples include the early KUMO robot which was modeled on a daddy-longlegs spider and was capable of excellent terrain adaptation. A second generation version of this system was the first stair climbing system in the world using tactile sensors. The modern series of TITAN walkers use a novel 3D pentagraph mechanism for energy efficient walking and are able to dynamically switch between static crawling and trotting.

Hannibal (Ferrell 1995), Genghis and Attilla (Brooks 1989) are examples of three legged walking robots that were built at the MIT AI lab. All three are behavior based. Hannibal in particular is interesting in that it has an extremely high degree of fault tolerance - a rare quality in autonomous walking robots.

Significant recent work on quadrupeds has been done by Jimenez et al. (de Santos & Jimenez 1995) and (Tsukagoshi, Hirose & Yoneda 1996). In (de Santos & Jimenez 1995) the authors describe a quadruped walker which walks in a stable discontinuous gait. The basic strategy is to use alternating tripods as support polygons. A similar set of stable walking strategies is demonstrated in (Tsukagoshi et

al. 1996) on the TITAN VII walking robot.

The problem of statically stable locomotion on legs is a challenging one when the terrain is uneven and footplacement must be planned based on sensor feedback. The above systems use different techniques to address this issue. In the case of Ambler and Dante the decision is made based on terrain geometry obtained by using a laser range finder. The early behavior based systems did not change their gait based on terrain features. Hannibal (Ferrell 1995) is a significant departure from this tradition.

2.4 Robot Evaluation

In this section we look at techniques used by past researchers to address the problem of robot evaluation. We divide these techniques into two categories.

1. The so-called "static" techniques which use arguments purely from statics to compare two robots.

2. "Dynamic" techniques which use information about robot–terrain dynamics and the control algorithms that are employed, to compare two robots.

We are primarily interested here in the second of these two categories though we review literature from both in following two subsections. This thesis is expected to contribute to the second category.

2.4.1 Static Evaluation Techniques

Static evaluation techniques have been so named here for two reasons. They are specifically designed for measuring stability when the robot is stationary and when it is moving in a statically stable fashion. The primary method of choice is an energy based stability measure as an evaluation function. In work by Nagy et al. (Nagy, Desa & Whittaker 1994) two modes of walker stability are characterized namely

stance stability and walker stability. Both use the amount of energy needed to destabilize the walking robot as a measure of the stability of the robot. Both modes were calculated for two test configurations under design consideration for outdoor exploration.

The (rigid) stance stability defined by Nagy et al. in (Nagy et al. 1994) is identical to the energy stability margin defined by Messuri et al. in (Messuri & Klein 1985). The energy stability margin was defined in (Messuri & Klein 1985) as the minimum work that must be done on a robot walker to tip it over an edge of a support boundary.

Early work on robot stability was due to McGhee et al. (McGhee & Frank 1968) who defined the support polygon as the convex hull of the projections of all contacting points on a horizontal plane. A walker was considered stable if the projection of center of gravity on the horizontal plane lay within the support polygon. Zhang et al. in (Zhang & Song 1989) defined the stability margin as the shortest distance between the projected center of gravity and the edges of the support polygon.

In (Mahalingam & Whittaker 1989) the authors define a conservative support polygon with the motivation that the walking robot should retain its stability in the event of a single leg failure. They consider n contact points with the ground. $n-1$ support polygons are constructed using all subsets (of size $n-1$) of the support points. The intersection of these subsets is defined by them as the conservative support polygon and the walker is considered stable if the projection of the center of gravity on the horizontal plane lies within it. Of the above energy based measures of stability the work of Nagy et al. is the most general since it includes compliance of the mechanism and depends on the terrain that is underfoot.

In (Bares & Whittaker 1993) the authors discuss several evaluation criteria for comparing three configurations for the design of a walking robot (Ambler). Some

of the evaluation criteria were foothold selection area, stride length, static stability and energy stability. According to the authors the important tradeoff was stride vs. stability. Based upon this they chose the circulating configuration for Ambler.

2.4.2 Dynamic Evaluation Techniques

Wilcox (Wilcox 1991) introduced a metric called the MCC (Mobility Characteristic Curve) to measure the ability of a robot to surmount obstacles. The obstacle was a cylinder of (theoretically) infinite length and diameter d which was buried to a depth $d/3$ in an inclined plane of slope s composed of loose sand. The MCC was defined as the plot with s on the horizontal axis and the diameter of the largest cylinder that the robot could surmount (in dimensionless units based upon its length) on the vertical axis. The proposed figure of merit was the area between the co–ordinate axes and the MCC. The two main achievements of this method were its independence of scale and easy reproducibility. Its chief drawback was that it used a simple obstacle geometry and did not evaluate the entire system in a mission oriented way.

Lietzau (Lietzau 1993) proposed a set of benchmarks to assess the performance of a Mars microrover. These benchmarks were divided into five categories namely, mobility, navigation and control, science, autonomy and environmental. A set of weights was assigned to these categories based upon their importance by the system designers and mission specialists. The weighted sum of the individual benchmarks was then proposed as a figure–of–merit. Lietzau's work is a thorough description of the individual subsystem tests that are a necessary part of evaluation but does not focus on the system level evaluation that we emphasize here. Though it was never formally characterized as such Lietzau's evaluation technique is an example of a LP approach to solve the problem of evaluation.

The main problem with doing isolated tests and then assigning a composite score using a weighted combination technique is that it presupposes the existence of

a good model for the combination and involves some amount of arbitrary assignment of weights.

2.5 Robot Modeling

Robot modeling has been heavily investigated. Typically one builds a model (a mathematical model simulated on a computer [4]) of a robot for two main reasons. They are

1. A good model facilitates the design of a better controller for the robot. In fact if the model is *perfect* then the controller design is greatly simplified.

2. A good model can be used in dynamic studies before the robot is built thereby leading to cost reduction and design improvement.

We are interested in the second reason here. A good robot model therefore should enable the designer to complete some part of the robot evaluation before the robot is built or deployed. We will review past work in robot modeling for both wheeled and legged robots. A vast body of literature exists on the modeling of robot manipulators. Since the present work is directed towards mobile robots we will look at the literature on manipulators to a much smaller extent. It is not advisable to ignore that work since mobile robots can be modeled with some of same techniques that are used in manipulators.

As will become clear in Chapters Three and Four, the technique we develop for robot evaluation will rely heavily on model building and simulation. We partition modeling into two parts, kinematics and dynamics.

[4]Typically one has to resort to computer simulation since the mathematical model is rarely solvable in closed form and must be integrated numerically

2.5.1 Kinematic Modeling

Kinematic modeling gives a description of the motion of the robot in terms of its generalized position and velocity. There is no explanation of the *cause* of motion i.e. the notion of force is absent. The other way of viewing this is that bodies have no mass or inertia and are able to sustain (possibly) infinite accelerations. In other words in purely kinematic modeling physical objects may instantaneously change velocities.

If q_i are the generalized positions which completely specify the robot's position and orientation and $\dot{q_i}$ are the corresponding generalized velocities then it is the business of kinematics to furnish us with their dependence on time. We seek therefore equations of the type,

$$q_i = q_i(t) \; ; \quad \dot{q_i} = \dot{q_i}(t) \tag{2.6}$$

It is customary in robotics to distinguish between the joint space and the Cartesian (workspace) of the robot. Let a point of interest on the (say n-DOF) robot be denoted by (x, y, z) in Cartesian space and corresponding generalized coordinates be $q_i, i = 1 \; to \; n$. The *inverse* kinematics of the robot express the $q's$ as function(s) of $x, y \; and \; z$. The *forward* kinematics of the robot express $x, y \; and \; z$ as functions of the $q's$. The 'point of interest' is typically the tip of a manipulator or the tip of the leg in the case of a walking robot. The generalized coordinates are typically the joint angles (in the case of rotary joints) and joint lengths (in the case of the prismatic joints).

The main simplification that most kinematic models make is the assumption that dynamic effects (as functions of time) due to masses and inertia are non existent or ignorable. An example of the application of kinematic considerations to a problem is footplacement for legged robots. In (Hirose & Kunieda 1991) the authors develop an algorithm to generate a foot trajectory for a quadruped using search areas and gait patterns. Motion planning problems such as the piano movers' problem (Hwang & Ahuja 1992) are examples of cases where a kinematic model of the robot suffices. In graphical interfaces the simulations depicted are often kinematic and motion is

caused by stepping through successive configurations using a simulation clock. An example of such work is (Koenig 1993).

Kinematic models are useful when the dynamics of the system are negligible. This is the case in a slow robot where the motion is essentially "quasi-static". In the case of complex robots on uneven terrain, where the energetics of the motion depend on the system dynamics, a kinematic model is not useful and a dynamic model must be built.

2.5.2 Dynamic Modeling

In dynamic modeling the mass and inertia properties of the robot are modeled in order to better capture the time behavior of the generalized coordinates of the robot.

As before if q_i are the generalized positions, $\dot{q}_i$ are the corresponding generalized velocities and Q_i are generalized forces acting on the body then the equations that describe the time behavior of the coordinates as a function of the forces acting comprise the dynamics of the system. These are usually differential equations which must then be solved to obtain q_i and $\dot{q}_i$ as functions of time.

For a 6-DOF robot manipulator with $q_1 \ldots q_6$ as its generalized coordinates these differential equations are conveniently written in matrix form as follows:

$$\mathbf{M}(\mathbf{q})\ddot{\mathbf{q}} + \mathbf{N}(\mathbf{q}, \dot{\mathbf{q}}) + \mathbf{G}(\mathbf{q}) = \mathbf{Q} \tag{2.7}$$

where $\mathbf{M}$ is the 6×6 (positive definite) inertia matrix, $\mathbf{N}$ is a nonlinear damping term and $\mathbf{G}$ is a potential term. For alternate formulations of these equations and efficient algorithms to implement them the reader is referred to (Featherstone 1987),(Lily 1993).

For walking robots one method to solve for the dynamics of the robot is to use the force-propagation technique developed by Cheng et al. In (Cheng & Orin 1991*b*) and (Cheng & Orin 1991*a*) the authors model the body of the walking robot as a "reference member" and propagate the components of foot force back to the reference member. This is done using Jacobian relations for the multiple chains (legs) that constitute the robot. The result is the desired angular and linear acceleration of the robot body. Contact with the environment is modeled as hard, point contact. The foot force constraints are made to satisfy friction constraints.

Solving the force distribution problem is important in dexterous robot hands. Kerr and Roth in (Kerr & Roth 1986*b*) and (Kerr & Roth 1986*a*) developed a model for force distribution in a robot hand. Friction was modeled but the finger inertias were ignored. Hsu et al. in (Hsu, Li & Sastry 1988) have modeled finger inertias also. In work on multi-legged vehicles Vijaykumar (Vijaykumar 1987) assumed hard point contact but did not include joint torque constraints.

Other work in dynamic modeling of hopping robots has been due to (Raibert, Jr. & Chepponis 1984), (Raibert & Wimberly 1984) and (Raibert 1986) which addressed the issue of controlling one leg with a prismatic joint first in two dimensions and then in three. The machine used by Raibert had two parts; a body and a leg connected to each other by a gimbal. The locomotion algorithm was found to elegantly decompose into three parts; forward running velocity control, body posture control and hopping height control. The dynamics of the hopping machine were developed by considering the body and leg as lumped masses with inertias. The gimbal was assumed to be ideal and friction with the floor was enough to prevent slippage. The dynamics were expressed as conservation laws of energy and momenta. In (Hodgins & Raibert 1990),(Hodgins 1991) the authors extended this work (using the same servo-control algorithms) to biped hopping machines. Raibert et al. were the first to show how "simple" the problem control really is in terms of a partitioned structure.

In (Cheng & Orin 1991*b*) and (Cheng & Orin 1991*a*) the authors develop an efficient formulation for the dynamics of closed-chain robotic mechanisms such as robot hands and legged robots in contact with their environments. Their formulation is general enough to include hard and soft contacts as well as contact with irregular environments. The basic idea in their approach is to model the kinematic structure as a tree with the robot body as the root node. Contact forces with the environment are then propagated back to the root using inverse Jacobian relationships for the links.

Sophisticated dynamic models have poor run time performance. However, for an application like the present work where evaluation studies can be done offline (there is no real time need), this does not present a problem. The advantages of using dynamic models are a better understanding of the system energetics and far greater scalability than kinematic models. This means that dynamic models can be used to study the system in a wide range of the state space whereas kinematic models are typically useful in cases where speeds are low.

2.6 Terrain Modeling

Terrain models for robots are usually elevation maps. The terrain is visualized as a function of two variables. This function is assumed continuous or discrete depending on the application. Typically, however, one has elevation samples at discrete intervals; therefore the continuous function is obtained by some kind of curve fitting technique such as a cubic spline, bicubic splines and Bezier curves.

A simple geometric terrain model is a function $z = f(x, y)$ where x and y are the coordinates along the base plane and z is the corresponding elevation. The main pitfall of such methods is that they capture only the geometry of the terrain and not its other characteristics such as friction coefficients, compliance and settlement.

Another method is to tessellate terrain into pixels or voxels (volume cells) and classify each pixel(voxel) based on its orientation, soil type etc.

A third technique is to transform the elevation data into another domain using say a Fourier transform. The main problem here is that while the original data has high resolution in the spatial domain it has poor resolution in the "frequency" or transformed domain. The reverse is true of the "frequency" domain. It has been shown (Daubechies 1992) that a particular class of transformations (called wavelet transformations) simultaneously provides high resolution in both domains. Some initial work on a compact representation of terrain geometry is reported in Chapter Four.

On board a mobile robot the main problem in building a terrain map is acquiring depth information from sensing. There are several different techniques that permit this. The first is acoustic (sonar) sensing where a pulse of sound is sent and bounced off the surface (ground) and the time taken for it to return is measured thereby providing the depth. The technique is subject to error due to specularity and irregular reflective characteristics of terrain. The second technique is to use a laser range finder. An excellent example of this is found in (Krotkov & Hoffman 1994) for the Ambler robot. The third technique is using vision. In order to get depth perception one approach that is used in computer vision is stereo vision. Stereo vision has problems associated with it such as registration. In the absence of a model the problem is even harder. In addition it is usually slow and not feasible for many mobile robot applications. In addition for extremely large scale terrain modeling photogrammetry is used. This is not yet a practical solution for the scale of interest in this study.

Once a geometric model of terrain has been achieved the problem of robot terrain interaction can be attacked. For a legged robot, terrain geometry alone is not enough to plan footplacement. Factors such as sinkage, slippage and compliance need to be

modeled to predict the dynamic effects of a footfall. The common approach (Manko 1992), is to model local leg terrain interactions as two springs perpendicular to each other, one tangential to the terrain at the point of contact and the other along the normal at the point of contact. Point contact is usually assumed. The first spring is intended to model slip and the second spring models sinkage. The values for these springs are determined empirically. Attempts to predict such constants using a physical model have been partially successful (Jimenez et al. 1993) where soil was modeled as a collection of small spherical aggregates rolling over each other.

Interaction between the leg/wheel and the terrain is difficult to model. In this study we simplify considerably and assume that friction at the contact is independent of the area of contact. We also assume that soil is nondeformable. The advantages of making these assumptions are simplicity and increased run time speed.

2.7 Navigation and Path Planning

Path planning and Navigation are fields abundant with results. In a short review of this nature we will be unable to do either of them justice. For a comprehensive review the reader is referred to (Hwang & Ahuja 1992).

Motion planning is the general term used for moving a robot from a start configuration to a goal. The term path planning is used to denote the process of finding a curve which connects the start position to the goal position in the workspace. When this path is parameterized in time it is called a trajectory. Trajectory generation for mobile robots is better known as navigation.

Amongst the many solution methods for path planning of particular note are potential field methods. Koditscheck (Koditscheck 1989) provides an excellent survey.

Free space techniques employing Voronoi diagrams (Canny 1988), Cell Decomposition etc. are some of the others. Path planning reduces to finding a connected sequence of feasible configurations from start to goal after a representation of free space has been chosen. Various search techniques such as Monte-Carlo (Barraquand & Latombe 1990), and dynamic programming (Dijkstra n.d.) have been developed which can be used to find such a sequence. We refer the interested reader to (Hwang & Ahuja 1992) for a comprehensive survey of motion planning in general with particular emphasis on path planning.

Navigation has been investigated by several researchers. Some examples are (Gat 1994), (Han & Rhee 1994), (Levitt & Lawton 1990) and (Roston & Krotkov 1991). In (Roston & Krotkov 1991) the authors develop a system for navigation by dead reckoning on a walking robot. In (Gat 1994) the author improves upon earlier work on Navigation Templates (NaTs). Most onboard navigation techniques rely on dead reckoning to keep track of current position and use a compass to keep track of current heading. Other techniques for navigation include beacons or landmarks (Han & Rhee 1994) or external devices such as GPS to supply the robot with current position information. The ability to navigate on a surface using local topology and landmarks is an area of active research in robotics especially since animals seems to do it so well. In our work we rely on a compass and dead reckoning using a shaft encoder to determine current position. This is prone to errors (integral errors due to slip which get propagated and are difficult to model), as further discussed in Chapters 4 and 5.

2.8 Mathematical Ecology

We have thus far surveyed kinematic and dynamic techniques for modeling robots. One can however conceive of a different modeling granularity - one which deals with robot motion in a statistical manner. Instead of asking where the robot is at a given

point in time one may ask where it is likely to be. This technique is likely to be useful where the simulated model is inaccurate for specific runs but the error envelope is distributed in such a way that errors balance each other over a large number of trials. One can now conceive of performing a number of trials with the simulated model and probabilistically answering the question about the position of the robot. The statistical predictions thus rely on a number of runs with an underlying kinematic (or dynamic) model.

Mathematical Ecology is an interesting field of research which deals with (among other things) spatial distributions of populations over time. We present here an interesting result concerning the spread of certain animal populations over time that have inspired us to hypothesize that robot motion may be statistically characterized as being diffusive.

In (Pielou 1969) and (Skellam 1951) the authors show that the spread of muskrats over time can be modeled as a diffusive process without drift. In (Broadbent & Kendall 1953) the spread of Helminth larvae are also shown to be diffusive. These ecological phenomena are thus believed to be governed by the diffusion equation

$$\partial\phi/\partial t = D\ \nabla^2\phi \tag{2.8}$$

where ϕ is the distribution of these populations with time, D is a diffusion constant and t is time. In the next Chapter we hypothesize a similar statistical model for robot motion over time and in Chapter 8 we show agreement between such a model and data collected from the experiments conducted in this study.

2.9 Summary of the Literature

In this Chapter we have presented a survey from various fields of research. The literature is rich in applications of multicriteria evaluation to many domains. This technique has not yet been applied to mobile robots. Further, several mobile robots

have been successfully designed, built and deployed but a systematic mission based evaluation methodology is missing. As a consequence, mobile robot evaluation and design is largely an art. Robot modeling techniques are well developed but are typically used for deterministic modeling for control or graphics. The current work applies sophisticated dynamic modeling techniques, statistically, to aid in multicriteria evaluation of mobile robots.

Chapter 3

The Problem Formulation

In the previous Chapter we listed several examples of robots built for outdoor exploration. We also reviewed examples of evaluation techniques and robot modeling. The goal of this Chapter is to develop a precise statement of the problem addressed in this thesis.

This Chapter is divided into two parts. In the first part we discuss a general formulation of the problem in terms of a class of mobile robots and a class of evaluation functions. In the second part we describe the particular class of robots of interest to us in this study. We conclude the Chapter by stating the research objectives of this work.

3.1 Designing an Evaluation Function

For a given mission with a well-defined goal(s) it is possible to disagree over what constitutes "good performance" for the robot. The notion of "goodness" is captured in an evaluation function. Designing an evaluation function from a mission statement is an issue that various researchers have analyzed under numerous guises.

We begin by identifying criteria that a good evaluation function should meet.

1. It should ideally capture as its input **all significant factors** that affect the robot's performance **and no others**. For example if one of the legs of the robot falls off, the performance of the robot is likely to be adversely impacted. On the other hand if the robot is painted green instead of blue it will in all probability not affect its abilities.

2. The output of an evaluation function should be much lower in dimension than its input. Typically therefore the output of an evaluation function is a scalar (usually referred to as the figure of merit).

3. It should be computationally tractable. If the evaluation function is computationally expensive then it is not practical.

4. It should be monotonic with respect to specific design parameters.

The problem of course is that these criteria are hard to satisfy in full generality. There is therefore a tradeoff in picking one evaluation function over another. In practice one picks functions that are practical to implement and capture as many significant inputs as possible.

One approach to the design of an evaluation function is to separate the problem into pieces (assumed independent) and then design an evaluation function for each piece. The figure of merit is then computed by taking a (possibly nonlinear) combination of the individual figures of merit using a weight vector as we saw in the previous Chapter. This approach is useful for practical reasons since it is easier to design evaluation functions for the constituents. The main problem is to find a good combination (weighting) function.

This technique suffers from some shortcomings. They are as follows

1. The design of each individual evaluation function suffers from the same problems enumerated above.

2. The combination of the various figures of merit is largely ad hoc.

3. The decomposition of the task into separate problems is largely ad hoc.

Our approach to the design of evaluation functions for mobile robots is discussed below. To begin with we need some representation for the robot and the evaluation function. We will represent a robot $\mathcal{R}$ and its environment as a 4-tuple $\langle \mathbf{y}, \mathbf{p}, \mathbf{q}, S \rangle$. The vector $\mathbf{y}$ represents the observable state of the robot. Elements of the vector $\mathbf{y} = [y_1, y_2, \ldots, y_n]$ could be for example the n joint angles, for an n-degree of freedom (DOF) robot. The complete state of the robot is represented by the vector $\mathbf{x} = [x_1, x_2, \ldots, x_m]$ where $m \geq n$. The elements of the vector $\mathbf{p}$ are the numbers that instantiate a particular robot. In other words the elements of $\mathbf{p} = [p_1, p_2, \ldots, p_k]$ are parameters such as robot length, width, mass, sensor range, ground clearance etc. The environment in which the robot is situated is parameterized by the vector $\mathbf{q} = [q_1, q_2, \ldots, q_l]$. The set S denotes the structure of the robot - i.e. its kinematic topology. We discuss the representation of S in the next section.

The robot behaves in accordance with the known laws of dynamics i.e. the vectors $\mathbf{y}$, $\mathbf{p}$ and $\mathbf{q}$ must satisfy the equations of motion

$$\dot{\mathbf{x}} = g(\mathbf{x}, \mathbf{p}, \mathbf{q}, t, w) \tag{3.1}$$

where t is time and w represents noise in the system and initial conditions are assumed to be known. The observable state vector $\mathbf{y}$ may now be written as

$$\mathbf{y} = h(\mathbf{x}, \mathbf{p}, \mathbf{q}, t, w) \tag{3.2}$$

g and h are m and n dimensional vector functions respectively. From now on when we refer to a robot $\mathcal{R} = \langle \mathbf{y}, \mathbf{p}, \mathbf{q}, S \rangle$ it will be implied that $\mathbf{x}$, $\mathbf{y}$, $\mathbf{p}$ and $\mathbf{q}$ satisfy Equations 3.1 and 3.2.

We define an evaluation function f as a map from the set of robots to the set of real numbers $\mathbf{R}$. An evaluation methodology is defined as a (finite) set of evaluation

functions written as $\mathcal{F} = \{f_1, f_2, \ldots, f_r\}$.

In Chapter One we presented a rough overview of the design and evaluation problems (see Figure 1.1). For most complex dynamical systems, model building involves solving (in most cases approximately) the equations of motions of the system. With the advent of fast computing in the last three decades this activity has come into its own. This is an exciting development since it enables us to build and test better evaluation functions than before. In the next section we propose a modular representation and simulation technique to simulate a broad class of robots.

3.2 Classes of Robots

Robots manipulators have been modeled as being kinematically equivalent to open chains (Cheng & Orin 1991*b*), (Cheng & Orin 1991*a*). Similarly mobile robots have been modeled as closed chains (Vijaykumar 1987). The dynamics of the robot are modeled by associating its mass and inertia properties with 'links'. Each link is then connected to one or more other links using joints. The joints are either active passive (unactuated) or active (actuated). Standard formulations of the robot dynamics are then written using well known techniques such as the recursive Lagrangian method (Hollerbach 1983) or the Newton-Euler method (Orin 1979).

As we shall see in the next section simulated models of robots can help us calculate the values of the evaluation functions and the evaluation Jacobian and can thus aid in evaluation and design optimization. We propose here a modular representation for mobile robots which is flexible enough to generate many useful and interesting members of the class of mobile robots. It is proposed that the simulated models of the mobile robots be built modularly using constituent modules and connection elements. The main purpose of this study is to measure robot performance using certain cost functions (details of which are given in Chapter Four). We have



Figure 3.1: The Wheel Module

used simulated models of the robots during the course of this work. In this Section we develop a representation to describe robot kinematics and then use this representation to define the precise class of robots we restrict ourselves to.

The wheeled robots that we will investigate in this study are composed of individual modules as shown in Figure 3.1. Each module is composed of two wheels and a (massless) axle. A chassis element is rigidly mounted on the axle. Each wheel has two degrees of freedom with respect to the axle. These are rotation about the z axis and about the x axis respectively. Each module is thus a 4-DOF element. The dynamics of such a module are simplified under the assumptions that the wheels are non-deformable and are in line contact with the ground; the axle and chassis are rigid and the axle is massless. It is also assumed that the element is symmetric and that the chassis is centrally mounted. The wheels are assumed to have equal mass. Each wheel is actuated by two identical semi-ideal actuators. By this we mean that the actuator dynamics are insignificant compared to the dynamics of the robot. However each actuator has a maximum limit on the torque that it can generate.



Figure 3.2: The Leg Module

Each module is thus parameterized by the following quantities - wheel inertia I_w, wheel radius R, wheel mass m, axle length w, chassis mass M, chassis inertia I_c and actuator maximum torque τ_{max}.

The legged robots that we will simulate in this study are composed of individual modules as shown in Figure 3.2. Each module is composed of two RRP[1] legs and a (massless) axle. A chassis element is rigidly mounted on the axle. Each leg has three degrees of freedom. These degrees of freedom are two rotations about the z axis and and translation along the z axis. Each module is thus a 6-DOF element. The dynamics of such a module are simplified under the assumptions that all the constituent links are non-deformable and that the feet are in point contact with the ground; the axle and chassis are rigid and the axle is massless. As in the wheeled case it is also assumed that the module is symmetric and that the chassis is centrally mounted. The legs are assumed to have equal mass. Each DOF is actuated by a semi-ideal actuator as before. Each module is thus parameterized by the following quantities - leg inertias I_{L1}, I_{L2} and I_{L3}, leg lengths l_1, l_2 and l_3, leg masses m_1, m_2 and m_3,

[1]RRP stands for rotational, rotational , prismatic - these are the joint types that make up the module (from proximal i.e. close to the body center, to distal)



Figure 3.3: The Connection Modules

axle length w, chassis mass M, chassis inertia I_c and actuator maximum torque τ_{max}.

A wheeled (or legged) robot is constructed using these modules and some "connection" modules. We restrict ourselves to the connection modules shown in Figure 3.3. All the connection modules are passive (i.e. unactuated) and are denoted by the symbols shown alongside them.

Each connection module also has some parameters. They are as follows:



Figure 3.4: Tree Structures of Some Robots

1. T (1 DOF translational joint): minimum and maximum extent written as q_{min} and q_{max}. The joint variable q satisfies $q_{min} < q < q_{max}$.

2. ϕ (0 DOF joint): this is effectively a massless rod which has only one parameter ie. length l.

3. R (1 DOF rotational joint): minimum and maximum angular extent written as q_{min} and q_{max}. The joint angle q satisfies $q_{min} < q < q_{max}$.

4. RR (2 DOF rotational joint): minimum and maximum angular extents written as $q1_{min}, q2_{min}$ and $q1_{max}, q2_{max}$. The joint angles $q1, q2$ satisfy $q1_{min} < q1 < q1_{max}$ and $q2_{min} < q2 < q2_{max}$.

5. RRR (3 DOF rotational joint): minimum and maximum angular extents written as qi_{min} and qi_{max}. The joint angles qi satisfy $qi_{min} < qi < qi_{max}$; $i = 1, 2, 3$.

In the canonical configuration all the joints shown in Figure 3.3 have length l. A compact and convenient way to represent a robot is to visualize it as a tree. The leaf nodes are the constituent modules described above. Each connection module plays

the role of a binary operator. In principle there is no reason not to have inhomogeneous leaf nodes. We will however restrict ourselves to the homogeneous case - where all the leaves are either wheel modules or leg modules. The kinematic structure of a robot S is represented by the corresponding tree. Two well known robots, the two robots used in this research, and their tree representations are given in Figure 3.4. For example the Rocky IV (a 6-wheeled rover designed and built at JPL) had three wheels on either side of the body axis. Each wheel had a corresponding opposite member on the other side of the body axis - thus each wheel pair corresponds to a wheel module (denoted W). The first two are rigidly connected to each other - i.e they have no DOF with respect to each other. This is shown by the joint ϕ in Figure 3.4. A third wheel module is then added to the first two using a 1 DOF passive rotary joint denoted by R.

Dynamic simulations of these modules were built and using the passive connection modules two interesting and representative members of the wheeled and legged classes (denoted as MENO and Marscar in Figure 3.4) were constructed and benchmarked using the performance metrics that we propose in this document.

Thus far in this Chapter we have developed a general representation for robot evaluation. We have also developed a tree structure representation for the kinematics of the systems under study. We have proposed that simulated models in conjunction with the physical robots under study can be used for evaluation and to perform local design optimization.

3.3 The Evaluation Jacobian

The evaluation methodology $\mathcal{F} = \{f_1, f_2, \ldots, f_r\}$ can be applied for local design optimization as well as evaluation and comparison of systems already built. In other words we can use the set of functions to partially order robot designs by evaluating

the values of the functions $\mathcal{F}$ for members of a class of robots. By restricting the definition of the robot class under evaluation it is not unreasonable to expect that one may be able to predict the performance of other (unbuilt) members of the class. Here is an example of an evaluation function f. Define the probability of reaching some distance s in time t to be $\pi(s,t)$. The integral of this distribution from time $t = 0$ to $t = t_0$, $\int_0^{t_0} \pi(s,t)dt$ is a function of distance s only. Integrating this function of s from 0 to some distance of interest s_0 one obtains a number (call it τ) given by $\tau = \int_0^{s_0} \int_0^{t_0} \pi(s,t)dtds$. τ is an example of an evaluation function f.

There are (potentially) three ways of finding the values of the functions $\mathcal{F}$ for a particular robot.

- Build the robot and perform empirical tests on it to evaluate all the functions $f_i; i = 1, \ldots, r$ for it.
- Construct an analytical model of the robot and obtain closed-form expressions for all the $f_i; i = 1, \ldots, r$ in term of the vectors $\mathbf{y}$, $\mathbf{p}$ and $\mathbf{q}$.
- Construct a simulation (which uses numerical techniques to solve the equations of motion for the robot), validate the simulation and evaluate the values of $f_i; i = 1, \ldots, r$ using it.

The first and third options seem reasonable for a system as complex as a mobile robot. It seems unlikely that the second option could be viable for a complex mobile robot with a realistic set of evaluation functions $\mathcal{F}$. Options one and three could be used in conjunction - the predictions of the computer simulated models could be validated using real robots and the data from empirical tests. We have followed this approach here. The computer models were tested and compared against situated robots.

The combination of the first and third options above (i.e. a validated computer simulation of the system) permits the calculation of the evaluation functions without empirical testing. In addition, parameter variations in the robot $\mathbf{\Delta p}$ and in the



Figure 3.5: Calculation of the Local Jacobian at a Particular Robot Configuration

environment $\mathbf{\Delta q}$ permit us to calculate the dependence of the evaluation functions on specific parameters by obtaining the partial derivatives $\partial f_i/\partial p_j$ and $\partial f_i/\partial q_j$ (at specific values of $\mathbf{p}$ and $\mathbf{q}$). The matrix of these partial derivatives is the Jacobian $\mathbf{J}$ of the mapping from the robot and environment parameters to the evaluation function output.

Using a locally linear approximation one can now estimate the change in each f_i (Δf_i) given a changes in $\mathbf{p}$ and $\mathbf{q}$ ($\Delta\mathbf{p}$ and $\Delta\mathbf{q}$).

$$\Delta f_1 = \frac{\partial f_1}{\partial p_1}\Delta p_1 + \frac{\partial f_1}{\partial p_2}\Delta p_2 + \ldots + \frac{\partial f_1}{\partial p_k}\Delta p_k + \frac{\partial f_1}{\partial p_1}\Delta q_1 + \frac{\partial f_1}{\partial p_2}\Delta q_2 + \ldots + \frac{\partial f_1}{\partial p_l}\Delta q_l$$

$$\Delta f_2 = \frac{\partial f_2}{\partial p_1}\Delta p_1 + \frac{\partial f_2}{\partial p_2}\Delta p_2 + \ldots + \frac{\partial f_2}{\partial p_k}\Delta p_k + \frac{\partial f_2}{\partial p_1}\Delta q_1 + \frac{\partial f_2}{\partial p_2}\Delta q_2 + \ldots + \frac{\partial f_2}{\partial p_l}\Delta q_l$$

$\ldots$

$$\Delta f_r = \frac{\partial f_r}{\partial p_1}\Delta p_1 + \frac{\partial f_r}{\partial p_2}\Delta p_2 + \ldots + \frac{\partial f_r}{\partial p_k}\Delta p_k + \frac{\partial f_r}{\partial p_1}\Delta q_1 + \frac{\partial f_r}{\partial p_2}\Delta q_2 + \ldots + \frac{\partial f_r}{\partial p_l}\Delta q_l$$

i.e.

$$\Delta \mathbf{f} = \mathbf{J}\Delta\mathbf{P} \tag{3.3}$$

where $\mathbf{P}$ is shorthand for the robot parameter vector $\mathbf{p}$ concatenated with the environment parameter vector $\mathbf{q}$. i.e. $\mathbf{P} = [\mathbf{p}|\mathbf{q}]$.

As a simple example let the robot parameter vector $\mathbf{p}$ be two dimensional. Let p_1 represent the length l of the robot and let p_2 represent the width w of the robot. Let the set of evaluation functions have two members namely f_1 and f_2 (their exact definitions are not important at this stage). The calculation of the evaluation Jacobian is shown pictorially in Figure 3.5. A nominal robot configuration is chosen; $\mathbf{p} = [l_0, w_0]$ and the values of f_1 and f_2 are calculated. The value p_1 is now changed to $p_1 + \Delta p_1$ i.e. $l_0 + \Delta l$. The resulting changes in f_1 and f_2 are measured. Call these changes Δf_1 and Δf_2. The ratios $\frac{\Delta f_1}{\Delta l}$ and $\frac{\Delta f_2}{\Delta l}$ are good approximations to the components of the first row of the Jacobian $\frac{\partial f_1}{\partial l}$ and $\frac{\partial f_2}{\partial l}$ if Δl is small enough. Similarly if a small change in p_2 (Δw) is made and the resulting changes in f_1 and f_2 are measured then one can find approximations to the second row of the Jacobian $\frac{\partial f_1}{\partial w}$ and $\frac{\partial f_2}{\partial w}$.

One can now perform local design optimization (ie. in the neighborhood of some $\mathbf{P_c}$, given by $|\mathbf{P} - \mathbf{P_c}| < \epsilon$) for a particular robot and environment parameterization using the Jacobian as follows.

We can visualize a discretization of the space around the point $\mathbf{P_c}$ (i.e. around a particular robot and environment). Each dimension of $\mathbf{P}$ (all the p_i and q_i) will be allowed to take one of 3 values namely $p_{i_c} - \epsilon/2, p_{i_c}, p_{i_c} + \epsilon/2$ and $q_{i_c} - \epsilon/2, q_{i_c}, q_{i_c} + \epsilon/2$. Since $\mathbf{P}$ had dimension $k + l$ this leads to $(k + l)^3$ discrete values for $\mathbf{P}$ in the above neighborhood. Assuming the Jacobian is constant over this neighborhood we will calculate the values f_i, $i = 1, 2, \ldots, r$ for each of these $(k + l)^3$ points using Equation 3.3. One can now order these $(k + l)^3$ different points (each of which is a different robot design in the neighborhood of the original point $\mathbf{P_c}$) according the

corresponding values of all the evaluation functions f_i, $i = 1, 2, \ldots, r$. The design which has the highest combined ranking over all r orderings is then the locally optimal design based on the evaluation functions $\mathcal{F}$. In this study we did two parameter variation studies and measured the relevant components of the evaluation Jacobian. The two studies were involved changes in the robot width and in the density of obstacles. We now introduce a particular example of a robot mission that we use as an example in this study.

3.4 The Robot Mission

The evaluation methodology that we propose here is for a particular robot mission - exploration of an unknown planetary surface. The area to be explored is assumed to contain rocks whose positions are not known *a priori* to the robot since it is presumed to be in unfamiliar surroundings. The robot mission is to perform scientific experimentation on rocks that are "interesting". We propose two evaluation functions in this study based on robot displacement as a function of mission time and energy consumption.

Figure 3.6 shows a schematic overhead view of the terrain to be traversed. The robot is started at the point R. The contours $1, 2, 3...$ are the *isochronal(or isoenergy)* contours. The locus of points which are equidistant in time-of-traverse from R is called an isochronal contour. In an analogous manner, the locus of points equidistant in energy-consumption from the point R is called an isoenergy contour. The shaded parts of the figure are obstacles.

The method of generation of these contours is to place the robot at R and command it to a goal at some given heading and a given radial distance. These two numbers (r, θ) define a goal for the robot in a global coordinate system fixed to the ground. The robot then attempts to navigate to this goal while negotiating obstacles. We will exploit the fact that this experiment can performed in both computer



Figure 3.6: Isochronal and Isoenergy Contours

simulation and using real robots constructed in the lab since this will permit us to benchmark more robot configurations and draw broader conclusions than with just two robots.

As we discuss further in the next Chapter the distribution of obstacles used in this study is a special one (the exponential Moore distribution). The Moore distribution is isotropic and equally unbiased towards all spatial coordinates. We thus expect that if the above experiment is run many times with different rock placements (drawn from the same exponential Moore distribution) then the averages of the contours will be concentric circles of increasing radii. Since there is good reason to believe that on the average it takes longer for the robot to go further the radius of a circle corresponding to a large value of time will be greater than the radius of a circle corresponding to a small value of time. A similar statement can be made regarding energy.

By merely taking the average of the contours we lose some information - instead we choose to capture the probability distribution of displacement from the start position as a function of time elapsed and as a function of energy consumption. These functions give us a statistical picture of what the robot performance is like on this terrain as a function of time(energy). The exact definitions of the metrics involve integrals of these probability distributions - the details are in Chapter 4. It may be noted here that studying the performance of the robots statistically is a strong argument for the use of computer simulation; one is able to do a larger number of runs than in practice (i.e. with situated robots) and one can make parameter variations in both the obstacle distribution and the robot parameters.

3.5 Three Hypotheses

In the chosen mission example the robot is tasked to go from a start position to a goal position. In the process it is expected to avoid any obstacles that it may encounter. The known feature of the environment is that the obstacles are in a certain distribution i.e. it is known *a priori* how many obstacles of a given diameter (or larger) are present in a given area. Given the robot's initial position (x_0, y_0), the goal position (x_g, y_g) we define the mission goal to be

$$d(robot, goal) \leq \epsilon \tag{3.4}$$

where $robot = (x(t), y(t))$ is the position of the robot centroid at time t , $goal = (x_g, y_g)$, $d(robot, goal) = \sqrt{(x(t) - x_g)^2 + (y(t) - y_g)^2}$ and ϵ is a small error margin. This is a motion planning problem where the planner is required to produce $x(t)$ and $y(t)$; functions of time that specify a trajectory that the robot can follow without colliding with obstacles. If the planner has a global world map then techniques exist in literature (Barraquand & Latombe 1990) and (Dijkstra n.d.) that can produce such a trajectory. In practice one needs to integrate dynamic constraints with the above problem. This has been studied in the kinodynamic literature



Figure 3.7: A Slice Through C-space

(Canny, Donald, Reif & Xavier 1988). If the planner does not have a global map of the world then reactive techniques (Gat 1994) exist that can be used for navigation.

In the following conjectures we will speak of the position of the robot as if it were a single point. To do this we visualize the robot as a point in a configuration space (C-space for short, see (Lozano-Perez 1990) for a good introduction to C-space) where the obstacles have been grown by the size of the robot (i.e. by taking the Minkowski sum of the robot and the obstacles). This is shown schematically in Figure 3.7. The basic idea behind a C-space representation is to view the robot and its environment in a space where the robot is represented as a point. In the case of a rectangular robot as shown in Figure 3.7 there are three numbers that uniquely specify where the robot is on the plane. They are the x, y position and θ, the angle that the major axis of the robot makes with the x-axis. The C-space representation thus has three dimensions namely x, y and θ. The robot is now a point in this three dimensional space and the obstacles are three dimensional solids. What is shown in Figure 3.7 is a slice through the C-space representation at a particular angle θ.

If the environment in the mission defined above was clear (free of obstacles) then no obstacle avoidance would be needed to complete the mission. The introduction of

an obstacle fundamentally increases the distance that the robot has to travel before reaching the goal (i.e. it reduces the probability that a straight line path between start and goal positions exists). We speculate that with more obstacles (or with larger obstacles) the deviation from the straight line path is greater and the robot has to travel a larger distance to reach the goal. Eventually the obstacle density may be high enough that the robot may never reach the goal. This case will not be considered in the current work - we will restrict ourselves to situations where paths to goal always exist.

In the early simulation phase of this study it was observed that statistically, the motion of the robot navigating to a pre-designated goal in an obstacle field resembles a diffusive process in time with a drift component.

$\phi_t(r,t)$ denotes the probability distribution of the robot displacement with respect to time where r is the robot displacement from its start location and t is time. D_t and c_t are coefficients of diffusion and drift respectively.

Hypothesis 1 *The distribution of displacement with respect to time can be modeled as a diffusive process given by the following equation:*

$$\frac{\partial \phi_t}{\partial t} = -2c_t \frac{\partial \phi_t}{\partial t} + D_t \, \nabla^2 \phi_t \tag{3.5}$$

We further hypothesize that the statistical behavior of the distribution of displacement with respect to energy is also diffusive. Let $\phi_e(r,e)$ denote the distribution of the robot displacement with respect to energy where r is the robot displacement from its start location and e is energy. D_e and c_e are coefficients of diffusion and drift respectively.

Hypothesis 2 *The distribution of displacement with respect to energy can be modeled as a diffusive process given by the following equation:*

$$\frac{\partial \phi_e}{\partial e} = -2c_e \frac{\partial \phi_e}{\partial e} + D_e \, \nabla^2 \phi_e \tag{3.6}$$

The two functions ϕ_t and ϕ_e differ because clearly $D_t \neq D_e$. At this stage it is not clear what D_t and D_e should be. The fraction of the land surface area that is covered by obstacles, the total perimeter of all the obstacles, the size of the robot relative to the obstacles are all likely to affect the values of D_t and D_e. In any case the values D_t and D_e are intended to model "resistance" of the environment to the diffusive process of robot motion. It may be noted that we are hypothesizing that the robot motion is diffusive only in a statistical sense i.e. we are interested in the first moments of the probability distributions ϕ_t and ϕ_e as functions of time and energy respectively. These moments are the expected values of displacement as functions of elapsed time and energy consumed as shown below.

$$\begin{aligned} < r(t) > &= \int_0^\infty r\phi_t(r,t)dr \\ < r(e) > &= \int_0^\infty r\phi_e(r,e)dr \end{aligned} \tag{3.7}$$

Hypothesis 3 *If the class of wheeled robots were evaluated using our metrics it would cluster in the 2-dimensional space spanned by the outputs of the two metrics. A similar statement holds for the legged class of robots.*

3.6 The Problem Statement

The general problem may now be stated as follows:

1. Given a class of mobile robots $\mathcal{R}$ and a class of evaluation functions $\mathcal{F}$, find members of $\mathcal{F}$ which enable classification of $\mathcal{R}$.

2. Use a combination of experiment and simulation to perform evaluation studies using selected members of $\mathcal{R}$ and $\mathcal{F}$.

3. Develop a methodology for extrapolation of robot performance beyond these instances chosen as examples.

4. Investigate (experimentally and in simulation) the hypotheses of the previous section.

These are the research goals of this thesis - their operationalization in terms of specific experimental tasks is the subject of the next Chapter.

Chapter 4

The Experimental Setup and Protocol

In this Chapter we introduce the two evaluation functions used in this work. We also describe the design of the wheeled and legged robots used for the experimental work; the simulated Mars environment facility which was specially constructed for the experiments and the control algorithms which were implemented on board the robots. The experimental protocol used to gather the data is also discussed. A significant part of the chapter is devoted to the design of the legged system because it was conceived and built in our laboratory whereas the wheeled systems are modifications of commercially available radio-controlled platforms.

4.1 The Cost Functions τ and η

The basic intuition behind the two cost functions proposed is to develop a nondimensional measure of the robot's ability to cover distance. The idea is to measure how "good" a particular design is by measuring how far it gets from the start location as a function of the time elapsed and the energy consumed by it. At first sight it may seem like the consumption of these two resources is extremely well correlated. This is indeed the case for straight-line travel on level ground with no obstacles. However, in the presence of obstacles it is not so - especially since the energy consumption of the system changes dramatically depending on whether it is at a standstill and



Figure 4.1: A Schematic of $P(r > r_0)$ vs. Time

thinking or whether it is moving.

A trial is defined as an autonomous traverse of the terrain by the robot in a particular instantiation of obstacle placement from start to goal. Using multiple trials we estimate the probability that the displacement $r > r_0$ for different values of the time t. A schematic of this probability as a function of time is shown in Figure 4.1. The main intuition is that the quicker this curve rises (close) to 1, the better the time utilization of the robot. Further, good time utilization also dictates that this curve be monotonic increasing. For the purposes of evaluation one is interested in the robot covering some displacement r_0 within some time t_0. In other words we expect some minimum performance for a limited resource (time).

The above requirement means that Robot A should be assigned a higher score than Robot B in Figure 4.2. This can be achieved by defining the area under the curve from $t = 0$ to $t = t_0$ as a metric. In order to compare robots of different size we measure displacement ($r = kl$) in terms of the number k of robot lengths l. We



Figure 4.2: A Schematic Comparison of $P(r > r_0)$ vs. Time for Robots A and B

also measure time in nondimensional terms by multiplying it with v/l where v is the robot velocity.

Let $\pi_{kl}(t)$ denote the probability of reaching a displacement kl as a function of time.

Definition 1 *The time figure of merit is defined as*

$$\tau = \int_0^{t_0} \pi_{kl}(t)dt \tag{4.1}$$

In a similar manner we plot the probability of reaching a displacement kl as a function of the energy e consumed. Energy is converted to a nondimensional quantity by dividing it by mgl where m is the mass of the robot and g is the acceleration due to gravity.

Let $\pi_{kl}(e)$ denote the probability of reaching a displacement kl as a function of energy.

Definition 2 *The energy figure of merit is defined as*

$$\eta = \int_0^{e_0} \pi_{kl}(e)de \tag{4.2}$$

Note than both figures of merit are non-dimensional.

4.2 The Legged Robot: MENO

4.2.1 Robot Design

MENO is a 12 DOF statically stable quadruped designed and constructed for this study in the USC Robotics laboratory. Each leg is a rotary-rotary-prismatic (RRP) design. The body of the robot and the first two links of each leg are in the horizontal plane and the prismatic joints (the most distal joint of each limb) are in the vertical plane. This orthogonal design was inspired by the design of Ambler (Bares & Whittaker 1993). The main advantages of such a design are ease of motion planning and energy efficiency. The robot chassis and limbs are constructed out of aluminum tubing. The robot is actuated by 12 off-the-shelf servomotors. A lead-screw is used to convert the rotation of the motor to vertical translation of the foot in the case of the prismatic joints. By retracting/extending the prismatic joints the chassis height above the ground is varied. Figure 4.3 shows the robot and Table 4.2.1 gives some of its mechanical parameters.

The robot is equipped with the following sensors

- **Foot switches:** Measure contact (on/off) with the ground. There is one on each of the 4 feet.

Table 4.1: MENO Mechanical Parameters

Quantity	*Value*
total mass	5 kg
chassis length	0.18 m
chassis width	0.15 m
proximal limb link length	0.09 m
distal limb link length	0.11 m
minimum height	0.14 m
maximum height	0.29 m

- **Two-axis inclinometer:** Measures the roll and pitch of the robot chassis with respect to the local gravitational vertical.
- **Resistive potentiometers:** One on each of the 8 rotational joints, to measure the joint angle.
- **Foot retraction microswitch:** To measure when a foot is fully retracted (on/off). There is one on each leg.
- **Compass:** Measures yaw of the chassis.
- **Foot obstacle contact switch:** To measure when a foot comes into contact with an obstacle during its swing phase. There are four (in parallel) on each foot.
- **Sonar:** Measures distance to obstacles. One forward looking transducer in the current implementation.

Onboard computing is all done on a custom board built around a Motorola 68332 microcontroller. A tether is used to supply offboard power for extended testing and for gathering telemetry. The testing is all done in a 3.5 m $\times$3.5 m sandbox. We describe the sandbox details later in this Chapter. The same sandbox is also used for experiments with the wheeled robots. Descriptions of the wheeled robots follow in the next section. A single camera suspended 3 m above the center of the sandbox



Figure 4.3: MENO in a Simulated Martian Environment

is used for tracking the robot's position. We do *not* use the overhead camera as a source of information for navigation; as we shall see in a later section navigation is done by dead reckoning using information measured by onboard sensors only. The sand surface is nominally flat but not precisely so. No attempt is made to smooth out the surface which is usually uneven as a result of people walking in the sandbox, depressions left by rocks that are constantly moved around and other disturbances. It should be noted that we are not dealing with excessive slopes or terrain that is likely to fail. Experiments and an analysis of the kinematics show that the maximum slope that the robot is able to navigate successfully is approximately 25^o.

4.2.2 The Control System

The Straight and Turn Gaits

The control system for MENO operates about a nominal gait. In order to generate the nominal gait the combined mass of the limbs, the chassis and the control



Figure 4.4: A Plan View of the Straight Gait (forward is towards the top of the page, numbers indicate stability margin in cm)

electronics was measured. Since these are the most massive parts of the robot the calculation of the center of mass uses only these values lumped at their geometric centers. For convenience they are shown on one limb only, as partially filled circles in Figure 4.7. Additional sensors that were added later were not used in making center of mass calculations for the nominal gait generation. The assumption was also made that the chassis and the first two links of each leg always lie in the horizontal plane. Further, the nominal gait generation also assumes ideal actuators and no slippage between the feet and the sand. The gait generation imposes the constraint that under the idealizations described above the projection of the center of mass of the robot onto the horizontal plane should lie in the support polygon formed by the stance feet (Messuri & Klein 1985). The term straight gait is used to denote a gait where the yaw of the robot chassis is constant. A turn gait serves to change the yaw of the chassis. It may be noted that the nominal straight gait presented here is similar to the intermittent crawl gait presented in (Tsukagoshi et al. 1996).

The nominal straight gait is shown pictorially in Figure 4.4. The first two phases (Figures 4.4a, 4.4b and 4.4b, 4.4c) are with 3 legs on the ground and are used to recover the 4th leg to a forward position. The 3rd phase (Figure 4.4c, 4.4d) is with all four legs on the ground and is used to move the center of mass of the robot forward with respect to the ground. The next three phases are mirror images of the first three.



Figure 4.5: A Plan View of the Turn Gait (forward is towards the top of the page, numbers indicate stability margin in cm)

The nominal turn gait example shown in Figure 4.5 uses small rotations to achieve a 10^o clockwise turn. The first phase of the turn gait shown in Figure 4.5 is 4.5a, 4.5b which rotates the chassis clockwise by 5^o while keeping all four feet on the ground. The second phase 4.5b, 4.5c is the recovery of the rear right leg to its new position. The third phase 4.5c, 4.5d is the recovery of the front right leg to its new position. In the fourth phase 4.5d, 4.5e the body of the robot is translated forward with all legs on the ground. Phase five shown in 4.5e, 4.5f is a clockwise rotation of the chassis by 5^o. Phase six is shown in 4.5f, 4.5g and is the recovery of the rear left leg to its final position. The final phase is the movement of the front left leg to its final position.

In both Figures 4.4 and 4.5 the numbers denotes the stability margin (in cm) prior to a swing phase. The + is the center of mass of the robot and the o is the geometric center of the support polygon.

The robot is thus designed to walk in a stable gait which is modeled as a state graph. The straight gait is the sequence of configurations labeled **S1** through **S6** in Figure 4.6. Forward motion of the robot is achieved by cycling from left to right in this graph. Moving from right to left causes the robot to move backward in a straight line. Every state shown as a rectangle in Figure 4.6 encapsulates a turn sequence composed of 8 states (7 phases) as described in the previous paragraph. The effect of transitioning through a rectangular box once is to turn the robot by



Figure 4.6: The State Graph

10^o (either to the left or right). Composition of turns leads to larger turn angles. Notice that it is not possible to turn from states **S2** and **S5**; to turn from one of these states we translate to a neighboring state and initiate a turn. It may be noted that the following correspondence exists between the state graph and the straight gait shown in Figure 4.4: **S1**-4.4a, **S2**-4.4b ... **S6**-4.4f. It may also be noted that the configuration shown in Figure 4.5a is the same as the configuration shown in Figure 4.4a which we call **S1** in the state graph. Figure 4.5h is the same configuration as Figure 4.4f; both are denoted by **S6** in the state graph. The example turn gait shown in Figure 4.5 is therefore the rectangle denoted **TR1-6** in Figure 4.6. The other rectangles contain similar sequences which cause the robot to turn.

Attitude and Gait Control

When the nominal gait is implemented on the robot with no feedback it fails almost immediately. Often before the robot completes one gait cycle it is destabilized enough to fall over while recovering a leg. The stability margin under which the nominal gait operates is small - see Figures 4.4 and 4.5. The center of mass location is quite sensitive to the configuration as shown below. We show a sample sensitivity calculation to estimate the amount of error δx_{cm} in the x position of the center of mass as a function of a small error $\delta\theta_1$ of the proximal joint angle. The center of mass along the local x axis (attached to the chassis) depends on the mass at locations A through E (Figure 4.7) and the mass of the chassis. The mass at A is the proximal servo motor which is fixed to the chassis. The configuration dependent mass moments are due to the mass at points B through E. We write only those terms (for one leg) explicitly below.

$$\begin{aligned} x_{cm} &= \frac{1}{M}(\frac{m_B a}{2}cos\theta_1 + m_C a cos\theta_1 + m_D(a cos\theta_1 + \frac{b}{2}cos(\theta_1+\theta_2)) + \\ &\quad m_E(a cos\theta_1 + b cos(\theta_1+\theta_2)) + \ldots) \end{aligned} \tag{4.3}$$

where $M = 5kg$ is the total mass of the robot, x_i denotes the x position of the point i in the chassis frame, m_i is the mass at point i, θ_1 and θ_2 are the proximal and distal joint angles as shown in Figure 4.7 and $a = 0.09$ m and $b = 0.11$ m are the link lengths. By differentiating the above with respect to θ_1 and bounding the sine and cosine values we conclude for small $\delta\theta_1$,

$$|\delta x_{cm}| \leq \frac{1}{M}(\frac{a}{2}m_B + a m_C + a m_D + \frac{b}{2}m_D + a m_E + b m_E)\ |\delta\theta_1| \tag{4.4}$$

Using measured values for the masses from MENO and the appropriate link lengths we have

$$|\delta x_{cm}| \leq 0.024\ |\delta\theta_1| \tag{4.5}$$

The measured errors in θ_1 on MENO are on the order of $\pm 10^o$. Substituting into the equation above we have the following error estimate

$$|\delta x_{cm}| \leq 0.0041 \ m \tag{4.6}$$

There are 8 rotational joints - if we assume that all of them are in error by 10^o then we have an upper bound on the error estimate $\delta x_{cm} \leq 8 \times 0.0041 = 0.0328$ m. This is an overestimate since the center of mass is not as sensitive to the distal angle θ_2 as it is to the proximal angle θ_1 but it serves as a good order of magnitude estimate. The above calculation was for the x component of the center of mass, a similar number for the y component may be assumed and the resultant error estimate in the center of mass position may be calculated as $\sqrt{2 \times 0.0328^2} = 0.0469$ m. This estimate exceeds the best stability margin available (see Figures 4.4 and 4.5). In light of the above calculation we may expect destabilization quite routinely when a leg recovery is attempted if the nominal gait is used without feedback. The reason for this is the play in the rotational joints. Further consider that there is unmodeled mass in the system in the form of new sensors, connectors etc. This mass is rigidly connected to the chassis and its moment does not depend on the configuration of the joints. However if it is asymmetrically mounted it introduces destabilization into the nominal gait which was derived without modeling it. Redesign of the robot with lighter materials for the legs and an indirect drive mechanism can be used to move mass closer to the chassis center thus increasing the stability margin. This introduces both cost and complexity into the design which we try to avoid. Further, simulation results show that with the current RRP design and conventional materials there is no substantial gain in stability with an indirect drive mechanism. A second solution lies in making small corrections to the nominal gait at every leg recovery if the inclinometers show excessive roll and pitch. This results in a slower walk but is much more reliable than the situation discussed above. This heuristic approach is adopted or MENO and is explained below.



Figure 4.7: MENO Parameters (plan view)

The magnitude of the correction to the nominal gait that needs to be made at each leg recovery is calculated using the inverse kinematics of each leg. The objective is to shift the center of mass away from the leg being recovered since the robot tilts towards the leg being lifted when the stability margin is exceeded due to joint errors. The assumption made is that the unmodeled mass is attached rigidly to the chassis. Hence if the chassis is moved away from the recovering leg the objective will be achieved. In Figure 4.8 we see two locations of the chassis and a leg. While the foot (point **T**) remains in contact with the ground the leg and chassis are moved from the solid line to the dashed line. Using the inverse kinematics it is possible to calculate appropriate final values for the two angles θ_1 and θ_2 given a desired shift in the geometric center of the robot $S = (\delta x, \delta y)$ and a desired chassis rotation λ. The same shift S and rotation λ is used for all four legs and the two angles are calculated for each leg separately. The new joint angles are then commanded to each rotational joint and the leg recovery is attempted again. If it fails the leg is lowered until contact and another shift is commanded. The leg is not recovered until it is safe to do so. It is worth pointing out here that this solution is not guaranteed to



Figure 4.8: A Shift Maneuver (plan view)

succeed; it may happen that in some configurations the commanded shift cannot be executed due to physical limits, singularities etc. In our experiments to date this has happened rather infrequently.

We are now ready to describe the complete control system as a set of interacting processes (see Figure 4.12). The sensor processes run at the fastest rate and may be considered as the lowest level processes. There is one process for each sensor and each updates a corresponding global data structure. The main control flow proceeds using an executive process that receives a command from a navigator. The navigator produces a nominal target sequence for the executive process to implement. It is described in the next subsection. No real time constraint is placed on the navigator which awaits a successful return from the executive process to advance its internal clock and produce the next target sequence. When attempting a leg recovery the



Figure 4.9: A Trace of MENO Power Draw During Walking

executive process treats it as a guarded motion and lifts the appropriate leg by a small amount until contact is lost with the ground. The resulting roll and pitch values are thresholded to estimate whether the robot is tipping or whether the leg can be recovered safely. In the latter case the leg is raised higher and the inclination is monitored. At any stage in the leg raise phase if the inclination exceeds a preset threshold the leg is lowered and a shift command is generated. The shift is executed with all legs on the ground and the leg recovery is attempted again. On completion of a shift or a successful leg recovery the `level()` process is executed.

The `level()` process tries to achieve two objectives: **a.** To level the plane of the robot, and **b.** To keep the centroid of the plane of the robot a certain (predefined) height above the ground in order to keep the operating region of the prismatic joints near the center of their region of travel. The `level()` process finishes when the roll and pitch values are below some preset thresholds.



Figure 4.10: MENO Pitch and Roll Regulation During Walking

The Navigation Algorithm

MENO navigates using dead reckoning interspersed with reactive obstacle avoidance. The basic strategy is to dead reckon using the kinematics of the robot and the appropriate transition along the state graph. The onboard compass is used to measure the direction of the chassis. Dead reckoning assumes that the chassis is horizontal and does not take into account the roll and pitch values. The robot is given a goal in world coordinates and is told its start location in the same world coordinate system. If an obstacle is encountered on the foot bumper switches the robot attempts to lift the leg higher to avoid the obstacle. If the leg is fully retracted and the obstacle is still in the way the robot backs up and turns. The front sonar is arranged so that it is triggered by large rocks which are insurmountable. The strategy used to avoid these large obstacles is to turn as soon as they are detected. If no obstacles are detected (either by the sonar or by the foot bumper switches) then the robot will attempt to walk forward provided the goal is in within an angular



Figure 4.11: Straight Gait Sequence ('forward' is to the right of the page)

Table 4.2: Arnold and Marscar Parameter Comparison

Quantity	*Symbol*	*Value*	
		Marscar	*Arnold*
total mass	m	5 kg	1.5 kg
chassis length	l	0.3 m	0.25 m
chassis width	w	0.3 m	0.16 m
wheel radius	a	0.075 m	0.04 m
turning radius	r	0.24 m	0.44 m
ground clearance	c	0.04 m	0.04 m
average speed	v	0.22 cm/s	0.22 cm/s

range of 30^o of the current forward direction as measured by the compass. If that is not the case a reorient procedure is initiated which turns the robot (essentially in place) thereby aligning it with the goal direction. The algorithm is essentially the same as the one employed on other reactive systems; (Gat 1995), and (Sukhatme & Bekey 1996) are examples. This algorithm is resident in the box labeled **Navigator** in Figure 4.12. A similar algorithm is used on board the wheeled robots and it is discussed in greater detail later in this Chapter.

4.3 The Wheeled Robots: Marscar and Arnold

Most of the experiments reported here were done on the bigger wheeled system called Marscar shown in Figure 4.13. The robot is 4 - wheeled rover with Ackerman steering.[1]

The front wheels are actuated together with a single motor. The same holds for the rear wheels. The robot is 0.4 m in length and 0.35 m in width. It stands 0.24 m high. It has a ground clearance of 0.04 m. Its total mass (with all sensors mounted)

[1]Ackerman steering maintains a particular relationship between the steer angles of the inner and outer wheels in order that the entire robot turn about a single point. The equations describing it are given in the next Chapter.



Figure 4.12: The MENO Control System Architecture

Figure 4.13: Marscar in a Simulated Martian Environment

is $5kg$. The kinematic parameters of the robot are summarized in Table 4.2. As in the case of MENO, all sensing and navigation decisions are made onboard. However the need for an elaborate balancing and guarded motion strategy is absent since the robot is inherently stable. Instability can only be caused by excessive terrain inclination which we do not address in this work. The power source (a high amp-hour $12V$ battery) is the only offboard component. The following sensors are installed onboard the robot.

- A digital compass which is interfaced to the microcontroller on board. The compass has a resolution of approximately 0.1^o.
- A forward looking sonar for detecting obstacles. The sonar is used to gauge distance to a frontal obstacle. Empirical tests show that it is accurate to within 5 cm for echos from rocks without any special postprocessing of the sensor reading other than averaging.

- Two forward looking infrared emitter/detectors pairs (IRs) which have a maximum range of 10 cm. These are binary sensors and are use to detect whether there is an obstacle directly in front of either front wheel.

- Two shaft encoders on the front and rear motor shafts which detect shaft rotation which is then converted to linear distance traveled by the wheels, assuming a constant wheel radius.

- A current sensor that measures the amount of current drawn by the robot. This sensor is accurate to 0.5% over the range 0-70 A.

The smaller wheeled robot is called Arnold. It was used in experiments to measure scaling effects on the metrics proposed in Chapter 3. The results of the scaling experiments are reported in Chapter 8. Arnold is a smaller version of Marscar and its kinematic parameters are summarized in Table 4.2. Arnold is equipped with exactly the same sensors as Marscar. The onboard controller is identical to the one employed on Marscar also. The smaller robot also runs exactly the same navigation algorithm. We describe Arnold in greater detail in Chapter 7.

The wheeled robots are programmed using a behavior based control system. The need to monitor pitch and roll is not there since these systems are stable on flat terrain. As in the case of the MENO control system, the sensor processes run asynchronously. There are two main behaviors which run at an approximate frequency ratio of 4 to 1. They are `avoid_obstacles_move()` and `reorient_to_goal()`. A schematic of the control architecture is shown in Figure 4.14.

In the next section we describe the common navigation algorithm used by all the robots in this study.



Figure 4.14: The Control Architecture for the Wheeled Robots

```
Loop until at goal:
     If obstacle in front
          Compute 'good' detour direction
          Detour
     Else
          If goal within angular range limits
               Move forward
          Else
               Reorient towards goal
          Endif
     Endif
EndLoop
```

Figure 4.15: The Navigation Algorithm

4.4 The Navigation Algorithm

Both kinds of robots described here use the same behavior based navigation algorithm. There are two basic behaviors; 1. Reorient towards goal and 2. Avoid obstacles. The basic idea is for the robot to keep track of its current position using knowledge of its kinematics and proprioceptive sensors (such as wheel encoders on Marscar and joint angle measurements on MENO). The estimator running on board the robot performs a simple dead-reckoning calculation to estimate position and orientation at every move. The 'avoid obstacles' behavior is also fairly simple - if an obstacle is seen the robot will attempt to detour around it (while keeping track of its position as mentioned above). If at the current time no obstacle is blocking the robot, it will attempt to move towards the goal, reorienting itself if necessary. The navigation algorithm is reactive in nature. A schematic outline of the algorithm is given in Figure 4.15.

An interesting part of the detour behavior is the use of global information. When an obstacle is detected the reactive strategy is to backup and turn. The direction of the turn is dependent on the current location of the robot and the commanded goal location in global coordinates. In Figure 4.16 we show an example. The robot (the wheeled system is shown as an example - the same strategy is used for both systems) is shown facing an obstacle (shaded). The commanded goal is marked **X**. The two strategies are marked **a** and **b** respectively. Strategy **a** changes the current angle of the robot from θ to $\theta - \delta\theta$ and strategy **b** changes the current angle to $\theta + \delta\theta$. The turn direction that reduces the difference between the robot angle and the desired goal angle θ_g is chosen and executed. A purely local strategy would pick one direction at random but the reactive obstacle avoidance behavior is modified to use some global information viz. the goal position.

We also adapt the angular range during a traverse. The basic observation is that small angular errors when the robot is far away from the goal lead to large position errors later. To avoid this we keep the angular range limits (within which no reorientation is necessary) small when the robot is far away from the goal. These limits are progressively increased as the robot nears the goal.

The average final position error due to the navigation algorithm in the case of Marscar is approximately 12% of the traverse length. For MENO the average navigation error is approximately 7% of the traverse length. The main difference between the two is due to the slip. In the case of Marscar the wheel slip is significantly higher than the foot slip in the case of MENO. In Figure 4.17 we show histograms of the error in the final positions of both robots.

In Figure 4.18 we show a typical traverse for each robot using the navigation algorithm described above. The circles denote rocks in both pictures. The MENO traverse is on the left. The goal is marked G and the start position is marked S. The robot position is shown by a succession of + signs. The plot on the right is a



Figure 4.16: The Detour Strategy (plan view): **a** is preferred over **b**



Figure 4.17: Navigation Accuracy for MENO and Marscar



Figure 4.18: A Typical Traverse for MENO and Marscar

sample Marscar run. The numbers denote position; the higher the number the more the time elapsed.

4.5 The Moore Distribution

The experiments done in this study were based on a model of rock distribution on Mars called the Moore distribution (Moore & Jakosky 1989). The Moore distribution predicts the numbers of rocks per unit area as a function of the rock diameter. The distribution also predicts the fraction of the surface area covered by rocks as a function of the rock diameter. The Moore distribution is an exponential relationship between the number of rocks per unit area and the corresponding rock diameters.

$$N = aD^{-b} \tag{4.7}$$

where N is the cumulative number of rocks per unit area and D is rock diameter. Equation 4.7 shows this relationship symbolically and Figure 4.19 shows plots



Figure 4.19: The Exponential Moore Distribution

of the Moore distribution for two values of the coefficient a; namely $a = 0.00415$ and $a = 0.013$. In both curves $b = 2.66$. The lower value of a corresponds to the so-called *Mars nominal* distribution in which most of the experiments of this study were done. This value is obtained by indirect thermal measurements of the planetary surface and represents a global average for the entire planet. The higher value of a is the so-called Viking II (or VII) model which used data from the Viking II lander to derive the higher value of the parameter a.

4.6 The Sandbox Facility

The experiments described in the following Chapters were done in a simulated Mars terrain comprised of a crushed red brick sand mixture. The mixture was spread evenly in a 3.5 m by 3.5 m sandbox to a depth of 0.25 m. The sandbox (called the Marsbox, shown in Figure 4.20) was populated with rocks of varying size (between 0.04 m and 0.2 m in diameter) to simulate Martian rock distributions. The density



Figure 4.20: The Marsbox with MENO and Marscar

of the rocks was equal to the Mars nominal density from the Moore distribution.

During the trials the robot was imaged using an overhead camera. The camera was suspended 3 m above the center of the sandbox and images taken by it were sent to a frame grabber attached to a Pentium PC. The analysis of the images to extract the position and orientation of the robot was done offline after the traverse was over. In order to correct the image distortion caused by the camera a pinhole model with a quadratic correction for distortion was used.

4.7 The Experimental Protocol

Earlier in this Chapter two metrics (τ and η) based on elapsed time and energy consumed were introduced. In order to experimentally measure the time and energy performance of the robots built in this study we use the experimental protocol described in this section. The evaluation functions use probability estimates from numerous mission trials. The experimental protocol therefore consists of many robot traverses from start to goal locations in different instantiations of Mars nominal Moore terrain. Some experiments were also done in VII terrain. The formal experimental protocol used in this study for the time trials is shown in Figure 4.21.

The basic idea behind the protocol is quite simple. There are three main loops. The experiments are done in different instantiations of Mars nominal terrain. Once a particular instantiation is picked the robot is situated in the Marsbox. In this particular instantiation a number of trials are performed with different start and goal locations. During the course of each of these trials (as the robot is navigating from start to goal) the offboard computer is monitoring time. When a certain time interval δ_t is reached the overhead vision system images the robot and the image is stored with a timestamp. When the current trial is over the sequence of images taken is postprocessed to extract the (x, y) location of the robot as a function of elapsed time. This information is stored in a file and the next trial begins. The procedure is terminated when all the exemplar start/goal locations have been used in every exemplar terrain.

Likewise the formal experimental protocol used in this study for the energy trials is shown in Figure 4.22. The protocol is exactly the same as the time trials but instead of monitoring the time elapsed, the power draw is monitored. Using this a running total of the energy consumed is maintained. When the energy consumption reaches a threshold δ_e the robot is imaged.

```
while <example terrains left>
   situate robot in new Mars nominal (VII)
   while <start and goal locations left>
      select new start and goal
      time_elapsed = 0
      while <robot is navigating to goal>
          monitor time
          if time_elapsed == delta_t
              image the robot (store x,y)
              time_elapsed = 0
          endif
      endwhile
   endwhile
endwhile
```

Figure 4.21: The Experimental Protocol for the Isochronal Measurements

```
while <example terrains left>
   situate robot in new Mars nominal (VII)
   while <start and goal locations left>
      select new start and goal
      energy_consumed = 0
      while <robot is navigating to goal>
          monitor power draw
          increment energy consumed
          if energy_consumed = delta_e
             image the robot (store x,y)
             energy_consumed = 0
          endif
      endwhile
   endwhile
endwhile
```

Figure 4.22: The Experimental Protocol for the Isoenergy Measurements

Once the data recording the position and orientation of the robot is obtained using the protocol described in Figures 4.21 and 4.22 it is processed to create plots of the required probability estimates that yield the previously defined figures of merit that we are interested in. The data processing steps for the time trials are as follows:

- Fix a given time resource value (t_0)
- Fix a required minimum displacement (r_0)
- Build a plot of $\pi(r > r_0)$ vs. t
    1. for each of the n data sets, $\forall t < t_0$ compute $r = \sqrt{(x - x_s)^2 + (y - y_s)^2}$
    2. a = number of r values greater or equal to r_0
    3. use a/n as the required probability estimate
- Compute nondimensionalized $\tau = \int_0^{t_0} \pi_{r_0}(t)dt$
- Repeat above steps for different values of r_0 and t_0

The data processing steps for the energy trials are similar and are given below for completeness:

- Fix a given energy resource value (e_0)
- Fix a required minimum displacement (r_0)
- Build a plot of $\pi(r > r_0)$ vs. e
    1. for each of the n data sets, $\forall e < e_0$ compute $r = \sqrt{(x - x_s)^2 + (y - y_s)^2}$
    2. a = number of r values greater or equal to r_0
    3. use a/n as the required probability estimate
- Compute nondimensionalized $\eta = \int_0^{e_0} \pi_{r_0}(e)de$
- Repeat above steps for different values of r_0 and e_0

In both outlines above (x_s, y_s) is the robot start location and $\pi(r > r_0)$ denotes the probability that the displacement r from the start location is greater than r_0.

Chapter 5

The Dynamic Simulation Models

In this chapter we discuss the details of the simulation models built during the course of this study. We discuss the simulation models and their validation for MENO and Marscar separately. This is followed by a section on sensor and actuator modeling. The chapter concludes with a description of the simulation environment used and other implementation details.

5.1 MENO Simulation

5.1.1 Chassis Dynamics

The MENO chassis is modeled as 13 interconnected rigid bodies. Each leg is composed of three rigid bodies namely the proximal link, the distal link (both of which are in the horizontal plane during walking) and the prismatic link which moves in the vertical plane. The chassis is connected to the proximal link of each leg. The robot is composed of a chassis connected to four legs thus leading to 13 rigid bodies and 12 controllable degrees of freedom. Each rigid body is modeled as a uniformly distributed mass. Each link and the chassis are modeled as cuboids of uniform mass distribution. The dimensions of each cuboid are the dimensions of the smallest bounding box of the corresponding link. The mass parameters were fixed using direct measurement of the mass parameters on the physical robot. Once the



Figure 5.1: The MENO simulated model (only the chassis and one leg is shown)

mass distribution and geometry of each link were fixed the moments of inertia were obtained by a simple calculation.

A schematic of the model is shown in Figure 5.1. Only the chassis and one leg are shown. The proximal link (labeled P) is attached to the chassis (C) using a single DOF rotational joint. The distal link (D) of each leg is attached to the corresponding proximal link using a single DOF rotational joint. The prismatic link (Pr) is attached to the distal link using a single DOF translational (prismatic) joint. The prismatic joint is composed of a single screw. The mass and size parameters of the leg links and chassis used in the simulation are given in Table 5.1.

5.1.2 Sensor and Actuator Models

All the sensors onboard MENO were modeled in simulation. The sonar and compass units were both modeled as Gaussian error distributions using data from the physical sensors available. Further discussion of these two sensors is deferred to the next section since these sensor models are common to both MENO and Marscar. Three

Table 5.1: MENO model parameters

Body	*Attribute/Value*	
ground	mass	∞
chassis	length	0.18 m
	width	0.15 m
	height	0.1 m
	mass	1.3 kg
proximal link	length	0.09 m
	width	0.02 m
	height	0.02 m
	mass	0.1 kg
distal link	length	0.11 m
	width	0.02 m
	height	0.02 m
	mass	0.2 kg
prismatic link	length	$0.14m$
	width	0.02 m
	height	0.02 m
	mass	0.08 kg

of the other sensors onboard the legged system are switches, namely: 1. A switch S_1 on each foot to detect contact with the ground 2. A switch S_2 on each leg to detect when the leg hits an obstacle and 3. A switch S_3 on each leg to detect when the leg is fully retracted. These 12 switches (3 on each leg) were modeled as perfect binary switches. The remaining sensor onboard the legged system (the most critical) is the two-axis inclinometer used to measure pitch and roll. This sensor is based on a liquid gel that has a characteristic settling time of 0.25 second (this figure is claimed by the manufacturer - a practical number is 0.5 second). The sensor was modeled as an exponential in time as shown in 5.1. Both roll and pitch axes were modeled using the same equation. $y(t)$ is the inclinometer signal in degrees; y_0 and y_f are the initial and final values of the signal and t is time in seconds.

$$y(t) = y_0 + (y_f - y_0)(1 - e^{-6.5t}) \tag{5.1}$$

All the actuators on board MENO are commercially available servomotors. They were modeled using critically damped PD servocontrollers. Two different servomotors were used. All 4 of the proximal motors (which actuate the proximal leg link) have a maximum torque of 1.2 Nm. The other 8 motors which actuate the distal leg links and the prismatic joint have a maximum torque of 0.6 Nm.

Each servomotor torque is modeled as the critically damped solution to a second order system. If θ denotes the angle of the servo at time t and θ_d denotes the desired final angle, then the behavior of the smaller servomotors is governed by

$$m(\ddot{\theta}) + b(\dot{\theta}) + k(\theta - \theta_d) = 0 \tag{5.2}$$

where $m = 0.1039$, $b = 0.36$ and $k = 0.1$. The behavior of the larger servos is governed by the same equation with parameters $m = 0.0118$, $b = 0.18$ and $k = 0.1$.



Figure 5.2: The Marscar simulated model. For convenience the angles θ_2, ϕ_2, θ_3 and ϕ_3 are not shown

5.2 Marscar Simulation

5.2.1 Chassis Dynamics

The Marscar simulation is composed of six rigid bodies, namely, the robot chassis, four wheels and the ground. The ground is modeled as a non-deformable object of infinite mass and inertia. The chassis and wheels are modeled as rigid bodies of the same dimensions as the physical robot. Figure 5.2 shows the simulated robot. The values given in Table 2 are used for the model parameters. The chassis is 'attached' to the ground with a 6 DOF joint thereby rendering it free to move with respect to the ground along (or about) any axis. Each wheel is attached to the chassis with a 2 DOF rotary joint. Thus each wheel is free to rotate about its own horizontal axis (spin) and about a vertical axis passing through its center (steer) as shown in Figure 5.2.

The first three equations below are the three constraints that relate the motion of the geometric center of the simulated vehicle to the motion of the wheels. Further,

Table 5.2: Marscar model parameters

Body	*Attribute/Value*	
ground	mass	∞
chassis	length	0.3 m
	width	0.3 m
	height	0.2 m
	mass	4.7 kg
wheel	radius	0.075 m
	thickness	0.1 m
	mass	0.07 kg

Ackerman steering is modeled using the three constraints in Equations 5.6, 5.7 and 5.8 that relate the steer angles of the front and back wheels and the rotation rates of the inner and outer wheels. See Figures 5.2 and 5.3 for the nomenclature.

$$\dot{X} = -\frac{2ar}{l} sin\phi_0 sin\beta \; \dot{\theta}_0 \tag{5.3}$$

$$\dot{Y} = \frac{2ar}{l} sin\phi_0 cos\beta \; \dot{\theta}_0 \tag{5.4}$$

$$\dot{\beta} = \frac{2a}{l} sin\phi_0 \; \dot{\theta}_0 \tag{5.5}$$

$$\phi_0 = -\phi_1 \quad \phi_2 = -\phi_3 \tag{5.6}$$

$$\dot{\theta}_0 = \dot{\theta}_1 \quad \dot{\theta}_2 = \dot{\theta}_3 \tag{5.7}$$

$$tan\phi_0 - tan\phi_2 = \frac{2w}{l} \tag{5.8}$$

Equations 5.6, 5.7 and 5.8 provide a formula for the turning radius r

$$r = \frac{1}{2}(w + l \; tan\phi_2) \tag{5.9}$$

In Figure 5.3 Oxy is the local coordinate system attached to the robot chassis and GXY is the global coordinate system attached to the ground. The angle between the two systems is denoted by β. Thus the position and orientation of the



Figure 5.3: A plan view of the simulated wheeled robot Marscar

robot is specified by (X, Y, β); ϕ_{0-3} specify the steer angles of the four wheels and θ_{0-3} specify the rotation (or spin) angles of the four wheels.

5.2.2 Sensor and Actuator Models

The sonar module is modeled using a Gaussian distribution. Experiments with the sonar unit show an average error of approximately 3 cm with a standard deviation of approximately 5 cm. The data from the sonar experiments was taken over a wide range of distances (0.1 m to 2.0 m) to the nearest obstacle as well as the full angular range of the sonar ($\pm 30^o$). Experiments over the full 360^o range of the compass

yield an average error value close to 0^o. Since our experiments with the physical robot were done indoors there were magnetic disturbances due to other equipment that caused sporadic errors up to approximately 10^o. The compass used is actually accurate to 0.1^o, but when used indoors in our experiments its performance is noticeably degraded from the original specification. For purposes of simulation the compass error was modeled as a Gaussian distribution with mean 0^o and standard deviation of 6^o. No attempt was made to model the systematic errors in compass performance due to the indoor location of the Marsbox. This is a significant factor in the differences between the dead reckoning performance of the simulation and the physical robot. The IR detectors are modeled as perfect binary sensors with a range of 5 cm.

Two actuators were modeled to drive the simulated robot. The wheels were steered using a servomotor of maximum torque $0.6Nm$. A critically damped PD controller was used to model this servomotor exactly like the model described in the previous section for the actuators on MENO. The drive motor was modeled as a linear speed/torque relationship for the range of speeds used in the current work.

5.3 Interaction with the Environment

In all the simulations reported here the terrain was assumed to be flat. The assumption was made that contact friction between the foot and the ground (in the case of MENO) and between the wheel and ground (in the case of Marscar) was independent of the area of contact. A single coefficient of static friction μ_s was used to model foot-ground interaction. Each of the feet on MENO is encased in a rubber sheet which is in direct contact with the ground. By experimental measurement μ_s between the feet soles and the sand was found to be 0.3.



Figure 5.4: Ground Friction as a Function of Rotational Speed

In the case of the wheeled robot two coefficients of friction were experimentally determined. Rolling friction at the ground/wheel contact was modeled as a constant for higher velocities and as a linear growth for small velocities. A similar profile was used to model friction between the drive shaft and the wheels. These values were inferred from experiments conducted with the physical robot on the sand surface of the Marsbox. Figures 5.4 and 5.5) show the values of the resulting frictional forces on Marscar as functions of the rotational velocity of the wheels.

During the course of the simulation there is a need to detect three kinds of contact events, namely: 1. MENO foot contact with the ground, 2. MENO foot contact with obstacle and 3. Marscar contact with obstacle. The first one is easy to do since it only requires monitoring the prismatic degree of freedom (the ground being assumed flat). In the more general case it would have to be done by checking the value of the prismatic joint against the height of the local ground under the foot. The general problem is quite complex and involves issues concerning efficient terrain representation. The second and third cases are solved using a two dimensional



Figure 5.5: Axle Friction as a Function of Rotational Speed

approximation and the flat ground assumption in order to perform them efficiently. Each foot on MENO is assumed to be a circle in the horizontal plane (this is a good a assumption - each physical foot is also circular). Each rock in the environment is assumed to be a sphere. Thus in the two dimensional horizontal projection contact can be computed efficiently since the intersection of two arbitrary circles can be solved efficiently in closed form. In the case of Marscar the assumption is made that if the minimum bounding circle of the robot intersects a rock then the robot is intersecting the rock also. Both cases are shown in Figure 5.6.

5.4 Implementation Specific Issues

The dynamic simulation of both robots was done using a tool called SD/FAST [1] which is used to generate code representing the dynamics of a set of interacting rigid

[1]SD/FAST is a trademark of Symbolic Dynamics, Inc. and Rasna Corporation



Figure 5.6: a. Contact between a MENO foot and a rock and b. Contact between Marscar and a rock

bodies. The specification of each (rigid) body is given by a 'joint' to the previous body (a selection of 9 joints is available) and the mass and inertia of the body. The joint set includes a 6 DOF joint to denote that successive bodies are free with respect to each other. Other joints include a hinge, a prismatic joint etc. SD/FAST generates 'C' code which is then integrated with user-written 'C' code to enforce constraints, contact geometry and control.

The code development was all done on a SUN Sparcstation UNIX system running SunOS 5.5. The basic flow diagram for both simulations is shown below in Figure 5.7. There are three main modules. The control module runs the global clock and monitors the sensor readings. The sensing module accepts the current robot state and the current world state as input and produces a set of sensor readings. The robot dynamics module accepts a current state as input, uses it to set initial conditions and then integrates the dynamics forward in time using a 4th order fixed step Runge-Kutta integrator. The final state (at the end of each integration interval) is returned



Figure 5.7: A flow diagram of the dynamic simulation

to the control module. The control module is responsible for the navigation strategy described earlier in this Chapter.

Chapter 6

Mobility Studies

In this Chapter we present the results of numerous mobility tests on both robots. The Chapter is organized by experiments done with the systems. For each experiment the data is shown and some conclusions are drawn - at the end of the Chapter a summary of the main results is given. We report results from experiments done in simulation and with the physical robots. Analysis of the two datasets shows their root-mean-square difference to be small compared to the standard deviation of either dataset. We begin the Chapter with a description of the statistical analysis.

6.1 The Statistical Analysis

In this study we need a statistical test that solves the goodness of fit problem given two datasets without knowing the functional form of either one. The reason is that we want to measure how well the displacement vs. time (energy) behavior predicted by the simulation corresponds to the displacement vs. time (energy) behavior measured from the experiments with the physical systems *without* assuming anything about the shape of either distribution. The required test is therefore non-parametric or distribution-free (Daniel 1978) and (Bradley 1968).

There is an additional constraint due to the nature of the datasets. Both sets of data are measurements of how average displacement changes with time (and energy).

Thus a particular value of average displacement at a given time t is *not* independent of the values of average displacement at times less than t. This presents a problem since most common non-parametric tests assume independence within a dataset. It is easy to find a parametric test which does not make this assumption but we have no *a priori* knowledge of the nature of the physical and simulated datasets and hence cannot use a parametric test.

The statistic we use for comparing the two datasets is the root-mean-square difference between them. This statistic is shown to be small relative to the average standard deviation of either dataset. Each dataset is an average displacement plotted vs. either time or energy. Thus at a particular value of time (or energy) the displacement has an average value and a standard deviation. We calculate the standard deviation at each value of time (or energy) and use the average of all these standard deviations in the comparison. This quantity is what we call the average standard deviation of each dataset.

Let the data consist of two independent samples of sizes m and n (let $m \leq n$). The observations are designated $X_1, X_2, \ldots, X_m$ and $Y_1, Y_2, \ldots, Y_n$ respectively. We call the X's the first sample and the Y's the second sample. The two samples are the average displacement values for the physical and simulated trials. Associated with each average X_i is a set of raw data denoted by $X_{i_1}, X_{i_2}, \ldots, X_{i_r}$ and associated with each average Y_i is a set of raw data denoted by $Y_{i_1}, Y_{i_2}, \ldots, Y_{i_r}$. Thus each average value X_i in the first dataset is given by

$$X_i = \frac{1}{r} \sum_{j=1}^{r} X_{i_j} \tag{6.1}$$

and each average value Y_i in the second dataset is given by

$$Y_i = \frac{1}{r} \sum_{j=1}^{r} Y_{i_j} \tag{6.2}$$

The root-mean-square difference between the two average datasets is given by :

$$d = \sqrt{\frac{\sum_{i=1}^{m}(X_i - Y_i)^2}{m}} \tag{6.3}$$

The standard deviation about the mean value X_i is given by

$$\sigma_{X_i} = \sqrt{\frac{\sum_{j=1}^{r}(X_{i_j} - X_i)^2}{r-1}} \tag{6.4}$$

and the standard deviation about the mean value Y_i is given by

$$\sigma_{Y_i} = \sqrt{\frac{\sum_{j=1}^{r}(Y_{i_j} - Y_i)^2}{r-1}} \tag{6.5}$$

Thus the average standard deviation for the first dataset X is given by

$$\sigma_X = \frac{\sum_{i=1}^{m}\sigma_{X_i}}{m} \tag{6.6}$$

and the average standard deviation for the second dataset Y is given by

$$\sigma_Y = \frac{\sum_{i=1}^{m}\sigma_{Y_i}}{m} \tag{6.7}$$

In the next Section we show that for every pairing of two datasets X and Y that we are interested in, the following relationships hold

$$\begin{aligned} d &< \sigma_X \\ d &< \sigma_Y \end{aligned} \tag{6.8}$$

This means that the mean 'difference' between the two datasets is smaller than the mean 'variance' of either one of them.

6.2 Mobility Trials in Mars Nominal

The first set of experiments that we report on here is a series of trials performed according to the experimental protocol described in Chapter 5. These trials were

done in different instantiations of a sparse obstacle distribution called the Mars nominal distribution. This translates to approximately 15 rocks of varying size in the Marsbox (which is approximately 12 m^2 in area). The environment parameters correspond to the Mars nominal density in the Moore distribution which were tabulated in Chapter 4. In Figure 6.1 we show a plot of average displacement vs. time for the wheeled robot Marscar. Each point on the plot is the average of 80 trials. All the trials were done in different instantiations of the Moore distribution corresponding to Mars nominal terrain. The same Figure also shows the results of trials with the Marscar simulator averaged over 200 simulated Mars nominal terrains. As one can see from the plots there is a close correspondence between the two curves. We reserve comment on the nature (shape) of the curves for now - that discussion will form the substantial part of Chapter 8.

While the curves in Figure 6.1 are *not* directly used in calculating the two figures of merit introduced earlier in Chapter 3, they are presented here to show the correspondence between the actual dataset and the simulated dataset. To rigorously establish this we calculate the the mean-squared distance d between the two datasets and the average values of their standard deviations σ_X and σ_Y. Calculations show that $d = 13$ cm, $\sigma_X = 40$ cm and $\sigma_Y = 44$ cm. Clearly, the two datasets in Figure 6.1 are very similar. This is encouraging since it increases confidence in the simulation.

We also use the same test to show the correspondence between the simulated dataset and the actual dataset in the case where displacement is considered as a function of energy. Those curves are shown in Figure 6.2.

In Figure 6.2 each point from the physical dataset is the average of 80 trials. As in the case of the time trials each point in the simulated dataset is the average of 200 trials. The experimental protocol used in both simulated and physical experiments was described in Chapter 4. As in the earlier case the data shown in Figure 6.2 is not directly used in computing the energy figure of merit. The data is presented



Figure 6.1: Average Displacement vs. Time for Marscar in Mars Nominal Terrain



Figure 6.2: Average Displacement vs. Energy for Marscar in Mars Nominal Terrain

here as evidence that the simulated and physical datasets are statistically similar. The values of d , σ_X and σ_Y summarize this similarity formally. Calculations show that $d = 10.2$ cm, $\sigma_X = 48$ cm and $\sigma_Y = 54$ cm.

In the case of the legged robot MENO, a similar correspondence between the simulated and physical datasets exists, both for the time trials and the energy trials. In Figure 6.3 a plot of displacement vs. time is shown for MENO in Mars nominal terrain. Each point in the real dataset is the average of 40 trials. In the simulated dataset each point is the average of 200 trials (all done in Mars nominal terrain). As is evident from Figure 6.3 a fairly good correspondence exists between the two curves. As in the earlier two cases with the wheeled robot Marscar we show statistically that the real and simulated datasets are in good agreement by calculating $d = 7$ cm, $\sigma_X = 53$ cm and $\sigma_Y = 49$ cm. Since we have $d < \sigma_X$ and $d < \sigma_Y$ we conclude that the two datasets are in good agreement.

In Figure 6.4 the two curves are plots of average displacement vs. energy for the physical and simulated walking robot in Mars nominal terrain. As in the time trials each point in the physical dataset is the average of 40 trials and each simulated point is the average of 200 trials. The protocols for the trials were described in Chapter 4. As before we calculate d, σ_X and σ_Y. We have, in this case $d = 10$ cm, $\sigma_X = 69$ cm and $\sigma_Y = 60$ cm which implies $d < \sigma_X$ and $d < \sigma_Y$ thereby establishing the similarity between the two datasets.

Thus far we have shown average results from trials in Mars nominal terrain with both robots. Results with the simulated robots are shown to be in good agreement with their physical counterparts. In the next Section we present an analysis of the simulated and physical datasets in accordance with the metrics τ and η proposed in Chapter 4.



Figure 6.3: Average Displacement vs. Time for MENO in Mars Nominal Terrain



Figure 6.4: Average Displacement vs. Energy for MENO in Mars Nominal Terrain

6.3 Clustering in Tradeoff Space

The trials done in Mars nominal distribution for both simulated and physical robots when analyzed according to the data analysis procedure described in Chapter 4 yield strong empirical evidence that the metrics proposed in this work partition the tradeoff space. To explain this we present the analysis of the datasets in a step by step fashion culminating in the tradeoff space visualization.

The first step in calculating the figures of merit is to calculate the probability of reaching k robot lengths as functions of time and energy. Since we have multiple trials we estimate this probability as the fraction of trials in which the displacement was greater than kl as functions of time and energy consumption. In Figure 6.5 the probability of Marscar reaching the threshold displacement kl is shown for various values of k. The quantity l is intended to be a measure (with dimensions of length) of the robot size. We use the cube root of the volume of the smallest rectangular box in which the robot can be packed. For Marscar $l = 0.35$ m. All the trials were done in Mars nominal distributions. One can see a reasonable agreement between the simulated dataset and the dataset collected from the physical robot. The simulated dataset consisted of 200 trials and the physical dataset consisted of 40 trials. The probability estimates of the simulated dataset are smoother compared to the physical dataset due to the larger sample size. The general behavior of the family of curves shown in Figure 6.5 is a monotonic rise to saturation. The interpretation of these curves is the likelihood of success (at navigating through the obstacle field) as a function of the available resource (time). A higher k value corresponds to a longer traverse and thus involves greater ability in penetrating obstacle fields. As k is increased for the same robot the probability of achieving the same degree of success decreases.

In Figure 6.6 a family of curves is shown which plot the probability of Marscar achieving a threshold displacement kl as a function of energy consumed. As in the case of the plots in the previous figure, the probability of greater success shows an



Figure 6.5: Marscar - Probability of reaching threshold displacements vs. time in Mars nominal terrain



Figure 6.6: Marscar - Probability of reaching threshold displacements vs. energy in Mars nominal terrain

asymptotic rise to saturation. Figure 6.6 shows the probability estimates for the simulated as well as physical datasets. As one can see there is a good match between the two. As in the previous case larger k values imply longer missions and thus are harder to achieve for the same value of the energy resource. Performance degrades as k is increased. As in the time trials with Marscar, the physical datasets in Figure 6.6 are the result of 40 trials and the simulated datasets are the result of 200 trials.



Figure 6.7: MENO - Probability of reaching threshold displacements vs. time in Mars nominal terrain

In order to compute the figures of merit for MENO in Mars nominal terrain we follow the same data analysis procedure as before. The curves showing the plots of the probabilities of achieving the threshold displacement kl as a function of time elapsed are shown in Figure 6.7. As in the previous cases increasing values of k signify longer missions. For MENO $l = 0.47$ m. The physical datasets shown in Figure 6.7 were computed using 40 trials in Mars nominal terrain and the simulated datasets were generated using 200 trials in simulation.

The last datasets of interest in the current series are the behavior of MENO as a function of the energy consumed in Mars nominal terrain. The relevant plots are



Figure 6.8: MENO - Probability of reaching threshold displacements vs. energy in Mars nominal terrain

shown in Figure 6.8.

In the notation of Chapter 4 we now have plots of $\pi_{kl}(t)$ and $\pi_{kl}(e)$; the probabilities of the achieving certain threshold displacements as functions of time and energy. Recall that the figures of merit defined in Chapter 4 are

$$\tau = \int_0^{t_0} \pi_{kl}(t)dt \tag{6.9}$$

$$\eta = \int_0^{e_0} \pi_{kl}(e)de \tag{6.10}$$

Table 6.1: The Figures of Merit for MENO and Marscar for Different Traverse Lengths

k	Marscar		MENO	
	τ	η	τ	η
2	14.7	11504	2.7	6911
4	12.1	11429	2.1	5957
6	9.4	9718	1.1	3609
8	7.3	9635	0.8	2745

where time t and energy e are converted to nondimensional quantities. Using $t_0 = 40$ min and $e_0 = 200$ kJ as representative numbers for the mission under study we calculate the two figures of merit using Equations 6.9 and 6.10 for different values of k. These values are shown in Table 6.1.

Figure 6.9 shows the τ and η values for the two robots in the tradeoff space. The lower left hand side of the plot (signifying lower evaluation scores) is the space occupied by the legged robot. The wheeled system has better scores on both time and energy axes. The evaluation functions are evaluated for 4 different values of k. Irrespective of the k value the wheeled robot outperforms the legged robot. The functions η and τ thus partition the design space.

To illustrate the cause of the difference in the evaluation scores it is useful to re-examine Figures 6.5 and 6.6 on the same scale. This is done in Figure 6.10 where we show the probability estimates for both MENO and Marscar with $k = 5$ as a function of the time elapsed. Seen on the same axis it is obvious that the wheeled system does better with the 'area under the curve' metric since it is a lot faster than the legged system in this terrain (the Mars nominal rock distribution).

If Figures 6.7 and 6.8 are plotted on the same axis a similar conclusion can be drawn regarding the energy scores. This is shown (again for $k = 5$) in Figure 6.11.



Figure 6.9: A Comparison of MENO and Marscar in Mars Nominal terrain for Different values of k



Figure 6.10: A Comparison of MENO and Marscar in Mars Nominal terrain for $k = 5$ as a Function of Time Elapsed

The wheeled robot needs far less energy to cover the same distance compared to the energy consumption of the legged robot over a similar distance for this particular rock distribution.

6.4 Sensitivity Studies - Robot Parameters

In this Section we report the results of experiments involving small parameter changes. Recall that in Chapter 3 we defined the evaluation Jacobian as a measure of the changes in the time and energy metrics when small changes are made to the robot design. We explore (in simulation) three parameter changes in both robots. The main finding is that the wheeled system is highly sensitive to width changes as well as changes in ground clearance. The legged system is not affected to a large degree by either. The main difference between the two systems is that the legged system has a ground clearance that is significantly higher than the wheeled



Figure 6.11: A Comparison of MENO and Marscar in Mars Nominal terrain for $k = 5$ as a Function of Energy Consumed

system. This means that the legged system is effectively facing an obstacle field of lower density than the wheeled robot (since fewer rocks are obstacles to the legged system). The wheeled system on the other hand is able to surmount very few (approximately 1 in 5) of the rocks in the terrain. A small change in its ground clearance dramatically improves its ability to go over rocks that were hitherto treated as obstacles. Similarly very often the wheeled robot is thwarted in its attempts to go between two rocks - this situation is alleviated with a small decrease in width.

6.4.1 Robot Width

Simulation studies with both MENO and Marscar in Mars nominal terrain yield the figures of merit shown in Figure 6.12. Three configurations were tested for each robot. The 'nominal' configuration for each robot had a width equal to the width of the physical system. The figures of merit for 'nominal width' are thus the same

Table 6.2: Elements of the Evaluation Jacobian for MENO and Marscar Calculated from Changes in Width

k	Marscar		MENO	
	$\frac{\partial \tau}{\partial w}$	$\frac{\partial \eta}{\partial w}$	$\frac{\partial \tau}{\partial w}$	$\frac{\partial \eta}{\partial w}$
2	43	29320	6.3	1603
4	66	40040	3.5	4853
6	61	38690	5.0	1806

as the ones in the previous graph shown in Figure 6.9. As one can see from Figure 6.12 the effects of change in width to the MENO evaluation scores is negligible. On the contrary there is clear improvement in both time and energy figures of merit for Marscar with decreasing width. This holds for various k values. The width changes made to each robot for these experiments were in increments of 5 cm.

In Figure 6.12 the Marscar scores are shown in three clusters. The middle cluster is the nominal configuration with width $w = 0.4$ m, the lower cluster is the simulated configuration with width $w = 0.45$ m and the higher cluster is the simulated configuration with width $w = 0.35$ m. The evaluation Jacobian components corresponding to these changes are given in Table 6.2.

6.4.2 Robot Ground Clearance

The second set of parameter sensitivity studies performed involved changing the ground clearance of both robots and measuring the effects on the mobility metrics. Effects of the changes in ground clearance on Marscar are fairly dramatic as seen in Figure 6.13. A small increase (5 cm) in the ground clearance of Marscar improved its ability to go over significantly more rocks than it before resulting a shorter paths to the desired goal. MENO performance is not significantly affected since its ground clearance is already high and the incremental advantage in clearing more rocks is



Figure 6.12: Effect of width change on MENO and Marscar in Mars Nominal terrain for different values of k

Table 6.3: Elements of the Evaluation Jacobian for MENO and Marscar Calculated from Changes in Ground Clearance

k	Marscar		MENO	
	$\frac{\partial \tau}{\partial c}$	$\frac{\partial \eta}{\partial c}$	$\frac{\partial \tau}{\partial c}$	$\frac{\partial \eta}{\partial c}$
2	12.2	29942	2.4	6084
4	35.1	25273	14.1	52462
6	76.1	50511	16.5	53709

smaller (there are few rocks of diameter larger than the ground clearance of MENO (28 cm) in Mars nominal terrain). Also the metrics penalize for size so the gain in size increase must be enough to compensate for the penalty in order for the mobility score to improve. Table 6.3 shows the values of the evaluation Jacobian for different values of k.

6.4.3 Robot Velocity

The legged system is significantly slower than the wheeled system. There are two main reasons for this. The first is intrinsic to the design where several joints have to be moved in sequence to achieve locomotion. The second reason is that the requirement of static stability implies constant monitoring of chassis roll and pitch. The inclinometer used to measure roll and pitch is a slow device. Its operation depends on the settling time of a fluid which which has a time constant of approximately 0.5 s. This was discussed in more detail in Chapter 5. This factor imposes a practical limitation on the speed at which the experiments reported here were done. However in simulation a faster sensor was modeled and the effects on the mobility of the legged robot were measured. The speed was increased by a factor of 2 for this experiment. The mobility scores on both axes improved due to the increased speed as shown in Figure 6.14.



Figure 6.13: Effect of change in ground clearance on MENO and Marscar in Mars Nominal for different values of k

The lowest left cluster in Figure 6.14 is the original MENO configuration with the slow inclinometer. The one to its immediate right is the simulated MENO configuration with increased speed.

6.5 Sensitivity Studies - Environment

As mentioned in Chapter 3 one of the objectives of this study was to measure the effects of changes in environmental parameters on the mobility metrics. The environment model used in this study is the distribution of rocks called the Moore distribution. In the vicinity of a previous mission to Mars (the Viking II mission) the density of rocks is much higher than the Mars nominal distribution used thus far. The effect of terrain clutter is very clearly seen in the two metrics. In the case of both robots, increased clutter leads to performance degradation. However it is interesting to note that the wheeled system is affected far more than the legged system. This is largely due to the fact that the increased clutter leads to significantly longer paths for the wheeled system whereas the legged system is able to go over many more obstacles and even though it is slower its performance is comparable to the legged robot. This is shown in Figure 6.15.

As one can see in Figure 6.15 the Marscar cluster moves dramatically to the left and down when the terrain was changed from Mars nominal to Viking II. MENO performance also suffered as seen in Figure 6.15 but not as dramatically. For this environment, its energy figure of merit is better than Marscar.

6.6 Scalarization of the Metrics

The metrics τ and η can be combined into a single scalar metric using a weighted linear combination. From the data presented in this Chapter we see that the wheeled



Figure 6.14: Effect of increased speed on MENO mobility in Mars Nominal terrain for different values of k



Figure 6.15: MENO and Marscar mobility in Viking II (cluttered) terrain for different values of k

robot outperforms the legged vehicle along both dimensions in Mars nominal terrain. The scalarization chosen should preserve this ordering. As we saw in the literature review presented in Chapter 2, a standard technique is to use a weighting function which is either linear or quadratic and maximize the combination of the two metrics. However the problem of how to choose the weights still remains. Instead of an ad hoc solution we use domain knowledge to postulate a feasible scalarization technique.

On one axis (τ) we are measuring the robot's ability to use time effectively and on the other (η) we measure effective energy utilization. The fundamental unit of conversion between them is the maximum power delivered by the onboard power source. If the power source is capable of delivering α W then we weight energy and time in the ratio $1 : \alpha$.

Table 6.4 shows the scalarized scores for $k = 6$ for the different cases reported in this Chapter using $\alpha_1 = 30$, $\alpha_2 = 40$ and $\alpha_3 = 50$. Using this scalarization technique the smaller width simulation of Marscar seems the most promising design in Mars nominal terrain. In dense obstacle distributions such as the Viking II site however the nominal configuration of the legged robot MENO is the better design using these metrics and this particular linear scalarization.

6.7 Discussion and Summary

In this Chapter we presented the data gathered from the time and energy trials during the course of the study. The protocol given in Chapter 4 was used for the data collection. The basic idea is to gather measurements of displacement as a function of elapsed time and energy consumed. These measurements are used to estimate the probability of achieving certain threshold displacements as functions of time and energy. The metric definitions given in Chapter 4 are used to calculate the figures of merit τ and η. The metrics were calculated from data calculated from tests with

Table 6.4: Linear Scalarization of the Metrics

Configuration	τ	η	$\tau + \eta/\alpha_1$	$\tau + \eta/\alpha_2$	$\tau + \eta/\alpha_3$
Marscar nominal	9.4	9718	333	252	203
Marscar low width	13.5	12402	426	324	262
Marscar high width	7.3	8533	291	221	178
Marscar high clearance	13.1	11143	384	292	236
Marscar in VII	5.6	947	37	29	25
MENO nominal	1.1	3609	121	91	73
MENO low width	0.96	2729	91	69	55
MENO low clearance	0.32	924	31	23	19
MENO faster	4.0	5346	182	137	111
MENO in VII	0.76	2698	91	68	55

the physical robots as well as in simulation. Statistical analysis shows a close correspondence between the data generated from the simulated models and the data measured from the experiments.

Values of the τ and η for Marscar are significantly superior to the MENO values. Parameter sensitivity studies show that the wheeled system is highly sensitive to changes in the width and ground clearance. The effect of obstacle clutter is also more pronounced on the wheeled robot. Experiments in simulation also show that if a faster walker were built it would perform significantly better. In the next Chapter we examine the effects of scaling on the mobility metrics.

There are three interesting aspects of the data presented here which form the basis for substantial future research. The first deals with the following design question: "In what parts of the design space are good designs found ?". At first glance it may seem like the answer is obvious - by definition it would seem like the designs leading to the highest values of the evaluation functions are the good parts of the design space. However, a closer look suggests that the real 'sweet spots' in the design space

are those where the design is insensitive to changes in the environment. For example, MENO in its nominal configuration is insensitive to changes in rock density. If there is large variability in the expected terrain density it may be a better decision to pick a design like MENO even though it has low evaluation scores compared to other designs. We are thus led to believe that future scalarization efforts should include weighted contributions from select components of the evaluation Jacobian in addition to the values of the evaluation functions themselves.

The second interesting point also concerns the evaluation Jacobian. Locations in the design space where the evaluation Jacobian becomes very large also provide interesting insight into design methodology. We suggest that these locations in the design space signal a 'breakdown' in the current kinematic design and a discrete jump to a new structure is indicated (with higher articulation perhaps or with a larger number of wheels).

A third application of the metrics proposed here is to global optimization. While the technique for extrapolating performance shown here is local, it is possible to extend it by instantiating a chain of local models and following the evaluation gradient to an optimal set of parameter values.

Chapter 7

Scaling Studies

As noted earlier, robot dynamics are notoriously nonlinear. It is therefore an interesting problem to examine the effects of gross changes in kinematic parameters on the metrics proposed in this study. During the course of this study a smaller wheeled system (called Arnold) was built and a validated dynamic simulation model of it was constructed. The simulation and physical robot were then used with the same protocol as with the larger wheeled robot Marscar and a comparative study was done. This Chapter briefly describes the smaller robot and the data collected from the study.

7.1 The Smaller Wheeled System - Arnold

The smaller wheeled robot Arnold is a four wheeled rover design. The main difference in its design and the design of Marscar is in size and steering mechanism. Arnold is smaller in width as seen from the comparison in Table 7.1. In all other respects it is essentially the same size. The steering on the two robots is also different. While both use Ackerman steering, Arnold turns using only the front two wheels while Marscar turns using all four wheels simultaneously. The difference in the turning radii is also seen in Table 7.1. Figure 7.1 shows the two turn geometries.

Table 7.1: Arnold and Marscar Parameter Comparison

Quantity	*Symbol*	*Value*	
		Marscar	*Arnold*
total mass	m	5 kg	1.5 kg
chassis length	l	0.3 m	0.25 m
chassis width	w	0.3 m	0.16 m
wheel radius	a	0.075 m	0.04 m
turning radius	r	0.24 m	0.44 m
ground clearance	c	0.04 m	0.04 m
average speed	v	0.22 cm/s	0.22 cm/s



Figure 7.1: Ackerman Steering on Marscar and Arnold

The same control system that ran on Marscar was employed on Arnold. Indeed the physical hardware used to control the bigger robot was used to control the smaller one. The smaller robot was equipped with the same sensor set namely Compass, Sonar and IRs.

In a scaling experiment ideally one would like all size dimensions to be scaled by a constant factor and examine the effects of the change. In our case we are interested in what happens to the energy consumption and time utilization metrics given a large change in size. However building an exact scaled replica of the bigger robot proved difficult given the constraints. The smaller robot used in the study is an off the shelf approximation to an actual scaled down version of the larger one. It is smaller in each dimension such as length, width, wheel radius and mass by different factors as seen in Table 7.1. A look at Table 7.1 shows that the two robots are not isometric as a true scaling study would require. Care was taken to ensure that the smaller system ran at the same speed as the bigger one. While the length and wheel radius of the two rovers are different; the significant differences in quantities are width and mass. The data reported in this Chapter is therefore largely a result of changes in these two quantities.

7.2 Comparison Data

The comparison between the two robots Marscar and Arnold was made in two situations. The first was the sparse Mars nominal rock distribution and the second was the cluttered Viking II distribution. The smaller robot performed better in both situations. Figures 7.2 and 7.3 show the results of this comparison. The data is analyzed in the next Section.



Figure 7.2: Marscar and Arnold in Mars Nominal terrain for different values of k



Figure 7.3: Marscar and Arnold in Viking II terrain for different values of k

7.3 Data Analysis

The smallest bounding box that can contain Marscar has volume 0.04 m^3. According to the definitions of the metrics τ and η given in Chapter 4, the size of the robot is measured in length dimensions as $\sqrt[3]{0.04} = 0.35$ m. A similar calculation for Arnold yields a size (expressed in dimensions of length) of 0.25 m. We subscript the Marscar variables by m and the Arnold variables by a. We denote the respective velocities of the robots by v_m, v_a; the masses by m_m, m_a; the sizes by L_m, L_a and the evaluation scores by τ_m, τ_a and η_m, η_a. Using $v_m = v_a = 0.22$ cm/s, $L_m = 0.35$ m, $L_a = 0.25$ m, $m_m = 5$ kg and $m_a = 1.5$ kg and the definitions of τ and η we have the following four equations.

$$\tau_m(k) = \frac{v_m}{L_m} \int_0^{t_0} \pi_{kL}^m(t)dt \tag{7.1}$$

$$\tau_a(k) = \frac{v_a}{L_a} \int_0^{t_0} \pi_{kL}^a(t)dt \tag{7.2}$$

$$\eta_m(k) = \frac{1}{m_m g L_m} \int_0^{e_0} \pi_{kL}^m(e)de \tag{7.3}$$

$$\eta_a(k) = \frac{1}{m_a g L_a} \int_0^{e_0} \pi_{kL}^a(e)de \tag{7.4}$$

Dividing Equation 7.1 by Equation 7.2, dividing Equation 7.3 by Equation 7.4 and substituting the values of the known quantities for the two robots given above we have the following two Equations relating the performance metrics of the two robots.

$$\frac{\tau_m(k)}{\tau_a(k)} = 0.71 \frac{\int_0^{t_0} \pi_{kL}^m(t)dt}{\int_0^{t_0} \pi_{kL}^a(t)dt} \tag{7.5}$$

$$\frac{\eta_m(k)}{\eta_a(k)} = 0.21 \frac{\int_0^{e_0} \pi_{kL}^m(e)de}{\int_0^{e_0} \pi_{kL}^a(e)de} \tag{7.6}$$

Equations 7.5 and 7.6 are the scaling laws for the metrics expressed in terms of the probability functions $\pi_{kL}(t)$ and $\pi_{kL}(e)$. Since the integrals of these functions appear explicitly in the above equations let us focus on them. For sufficiently large values of t_0 and e_0 in a terrain where paths to goal exist the functions $\pi_{kL}(t)$ and $\pi_{kL}(e)$ saturate to 1 at time $t \ll t_0$ and energy $e \ll e_0$. In this case we have

$$\frac{\int_0^{t_0} \pi_{kL}^m(t)dt}{\int_0^{t_0} \pi_{kL}^a(t)dt} \to 1 \tag{7.7}$$

$$\frac{\int_0^{e_0} \pi_{kL}^m(e)de}{\int_0^{e_0} \pi_{kL}^a(e)de} \to 1 \tag{7.8}$$

The condition that the functions $\pi_{kL}(t)$ and $\pi_{kL}(e)$ are saturated is satisfied for short traverses ($k < 5$) by both Arnold and Marscar. Equations 7.5 and 7.6 reduce to the following ratios.

$$\frac{\tau_m(k)}{\tau_a(k)} = \frac{L_a}{L_m} = 0.71 \tag{7.9}$$

$$\frac{\eta_m(k)}{\eta_a(k)} = \frac{m_a L_a}{m_m L_m} = 0.21 \tag{7.10}$$

A comparison with the data exhibited for various values of k shown in Figure 7.2 yields the numbers given in Table 7.2. If the density of the two robots was the same then we would expect the the ratio of the masses m_a and m_m to scale as the cube of the ratio of the length-like quantities L_a and L_m. This implies that the energy figure of merit scales as the fourth power of the length-like quantity and the time figure figure of merit scales linearly with the length-like quantity.

$$\begin{aligned} \tau &\propto L \\ \eta &\propto L^4 \end{aligned} \tag{7.11}$$

Table 7.2: Predicted Values of τ and η Ratios Compared to the Measured Values

k	$\frac{\tau_m(k)}{\tau_a(k)}$	$\frac{\tau_m(k)}{\tau_a(k)}$(calculated)	$\frac{\eta_m(k)}{\eta_a(k)}$	$\frac{\eta_m(k)}{\eta_a(k)}$(calculated)
2	0.81	0.71	0.29	0.21
4	0.74	0.71	0.29	0.21
6	0.63	0.71	0.25	0.21
8	0.55	0.71	0.24	0.21

7.4 Summary

In this Chapter scale effects were discussed. The main result is that for sufficiently large values of the time and energy available the scaling laws are simple to write down. True scaling would involve isometric studies where the density of the two robots would be kept constant and all length dimensions changed by a fixed factor. We include such an effort as part of the suggestions for future work given in Chapter 9. The other interesting fact is that the main reason for the improvement in the performance of the smaller wheeled robot over the bigger one is its reduced mass. The length dimension changed from 0.35 for Marscar to 0.25 for Arnold but the mass changed from 5 kg to 1.5 kg which is a bigger change than what is required by the equal density assumption.

Chapter 8

Diffusion Modeling

In this Chapter we show that the average displacement of the robot under the control of a reactive navigation algorithm looks like a diffusive process. This simple model fits the data collected from the experiments described in the earlier Chapters.

8.1 Review of Diffusive Processes

Before proceeding further we give a brief review of diffusive processes. The simplest form of diffusion is the bulk motion arising from individual random walks. The classic example is a gas system composed of many molecules. Each molecule is modeled as an independent entity whose motion in a straight line at constant speed is uninterrupted until it hits another molecule. The result of such a collision is that both colliding molecules suffer an abrupt (modeled as instantaneous) change in their velocity vectors. The assumption is that the change in the direction of the vector is random. Typically there are external forces present and these are superimposed on the diffusive motion in the form of drift. The resulting motion is called diffusion with drift. It is possible to derive expressions that correspond to the change in density of a gas over time at some particular point of space or to calculate the change in density over some region of space at some particular instant of time. In recent years mathematical models have become popular in ecology. Aggregate animal behavior and dispersal patterns have been modeled using diffusion equations (Pielou 1969)

and (Okubo 1980). The basic equation for modeling a diffusive process is called the Fokker-Planck equation (first derived for Brownian motion by Fokker and Planck in the early part of this century). Since then it has been widely studied and applied. For a comprehensive review see (Risken 1984).

We begin by exhibiting a brief derivation of the one-dimensional diffusion equation with drift. The treatment is adapted from (Pielou 1969). Consider an agent (migrating animal, gas molecule, robot) moving along a line executing a random walk. Suppose at $t = 0$ the agent was at $x = 0$. At each time instant the agent takes either a step to the right (causing x to increase by 1 unit) or a step to the left (causing x to decrease by 1 unit). Assume that the probability (at any time instant) of stepping to the right is p and the probability of stepping to the left is $q = 1 - p$. Denote by $\phi(x, t)$ the probability that at time t, the agent is at x. The following difference equation holds.

$$\phi(x, t + \Delta t) = p\phi(x - \Delta x, t) + q\phi(x + \Delta x, t) \tag{8.1}$$

Let us expand both sides of Equation 8.1 in Taylor series. Also abbreviate $\phi(x, t)$ to ϕ.

$$\phi + \frac{\partial \phi}{\partial t}\Delta t + \frac{1}{2!}\frac{\partial^2 \phi}{\partial t^2}(\Delta t)^2 + \cdots = \phi + (q - p)\frac{\partial \phi}{\partial x}\Delta x + \frac{1}{2!}\frac{\partial^2 \phi}{\partial x^2}(\Delta x)^2 + \cdots \tag{8.2}$$

Dividing through by Δt we have

$$\frac{\partial \phi}{\partial t} + \frac{1}{2!}\frac{\partial^2 \phi}{\partial t^2}\Delta t + \cdots = (q - p)\frac{\partial \phi}{\partial x}\frac{\Delta x}{\Delta t} + \frac{1}{2!}\frac{\partial^2 \phi}{\partial x^2}\frac{(\Delta x)^2}{\Delta t} + \cdots \tag{8.3}$$

Now let $\Delta x \to 0$ and $\Delta t \to 0$ with the condition $(p - q)\Delta x/\Delta t \to 2c$ and $(\Delta x)^2/\Delta t \to 2D$ where c and D are parameters. All higher derivatives tend to zero.

Equation 8.2 reduces to:

$$\frac{\partial \phi}{\partial t} = -2c\frac{\partial \phi}{\partial x} + D\frac{\partial^2 \phi}{\partial x^2} \tag{8.4}$$

This is the Fokker-Planck equation describing one-dimensional diffusion with drift. The solution to this equation is given by the normal distribution:

$$\phi(x,t) = \frac{1}{\sqrt{4\pi Dt}} e^{-\frac{1}{4Dt}(x-2ct)^2} \tag{8.5}$$

The solution for the two dimensional case can be derived in a similar manner; we write the two dimensional Fokker-Planck equation and its solution below.

$$\frac{\partial \phi}{\partial t} = -2c(\frac{\partial \phi}{\partial x} + \frac{\partial \phi}{\partial y}) + D\nabla^2 \phi \tag{8.6}$$

$$\phi(x,y,t) = \frac{1}{4\pi Dt} e^{-\frac{1}{4Dt}((x-2ct)^2+(y-2ct)^2)} \tag{8.7}$$

8.2 Displacement vs. Time Model

For our problem we are interested in the radial dependence of displacement vs. time. Convert to polar coordinates using $x = rcos\theta$, $y = rsin\theta$ and $dxdy = rdrd\theta$. Equation 8.7 can be rewritten as:

$$\phi(r,\theta,t) = \frac{r}{4\pi Dt} e^{-\frac{1}{4Dt}(r^2+8c^2t^2-4ct(rcos\theta+rsin\theta))} \tag{8.8}$$

Let us consider the case with no drift i.e. $c = 0$. This gives:

$$\phi(r,\theta,t) = \frac{r}{4\pi Dt} e^{-\frac{r^2}{4Dt}} \tag{8.9}$$

Recall that ϕ is probability of the agent being at (r, θ) at time t. Integrating over θ gives the probability $\phi(r, t)$ of the agent being at r at time t:

$$\phi(r,t) = \frac{2r}{a^2 t} e^{-\frac{r^2}{a^2 t}} \tag{8.10}$$

where $a^2 = 4D$. This is a probability distribution of r as a function of time t. A quick check shows that the function is normalized i.e. $\int_0^\infty \phi(r,t)dr = 1$. The quantity of interest to us is the expected value of r (denoted by $< r >$) as a function of time t. The expected value of a variable whose normalized probability density function is known is given by the first moment of the pdf. Thus

$$< r(t) > = \int_0^\infty r\phi(r,t)dr \tag{8.11}$$

Simplifying we obtain

$$< r(t) > = a\Gamma(\frac{3}{2})\sqrt{t} = \frac{a\sqrt{\pi}}{2}\sqrt{t} \tag{8.12}$$

If the process is drift free, the expected value of displacement over time grows as the square-root of the time elapsed. Equation 8.12 was fitted to the average displacement of both Marscar and MENO in Mars nominal terrain. The results as shown in the Figures 8.1 and 8.2. As one can see the fits are fairly good. Each fit is governed by the single parameter $a = 2\sqrt{D}$. For Marscar $a = 5.9$ ($D = 8.71$ cm^2/s) and for MENO $a = 1.83$ ($D = 0.84$ cm^2/s). However intuition suggests that better fits may be obtainable if a drift term were included. After all both robots were under the control of navigation algorithm which was implementing a goal seeking behavior. Conceptually we may think of this as an attraction towards the goal thereby introducing a drift term into the model. For this we go back to Equation 8.8 rewritten below for convenience.



Figure 8.1: Average Displacement of Marscar as a Function of Time Fitted to a Diffusive Model



Figure 8.2: Average Displacement of MENO as a Function of Time Fitted to a Diffusive Model

$$\phi(r,\theta,t) = \frac{r}{4\pi Dt} e^{-\frac{1}{4Dt}(r^2+8c^2t^2-4ct(rcos\theta+rsin\theta))} \tag{8.13}$$

The problem now is to evaluate the following integral to factor out the θ dependence.

$$\phi(r,t) = \int_0^{2\pi} \phi(r,\theta,t)d\theta = \int_0^{2\pi} \frac{r}{4\pi Dt} e^{-\frac{1}{4Dt}(r^2+8c^2t^2-4ct(rcos\theta+rsin\theta))} d\theta \tag{8.14}$$

This produces the following function[1] for $\phi(r,t)$

$$\phi(r,t) = \frac{r}{2Dt} I_0(\frac{\sqrt{2}c}{D}r) e^{-\frac{(r^2+8c^2t^2)}{4Dt}} \tag{8.15}$$

where $I_0()$ is a modified Bessel function. $< r(t) >$ is thus given by

$$< r(t) > = \int_0^{\infty} \frac{r^2}{2Dt} I_0(\frac{\sqrt{2}c}{D}r) e^{-\frac{(r^2+8c^2t^2)}{4Dt}} \, dr \tag{8.16}$$

Unfortunately this is not integrable in closed form. However numerical approximations show that the expected value $< r(t) >$ can be approximated as the sum of two terms, namely a square root dependence and a linear term. This means that $< r(t) >$ is now modeled as:

$$< r(t) > = a\Gamma(\frac{3}{2})\sqrt{t} + bt = \frac{a\sqrt{\pi}}{2}\sqrt{t} + bt \tag{8.17}$$

b is a drift parameter. If Equation 8.16 were integrable in closed form and led to a closed form expression for $< r(t) >$, it might have been possible to write b as a closed form function of c (the drift parameter previously defined). For this treatment we make the assumption that b is the new drift parameter which is some complicated function of of the old drift parameter c. The best fit curves to the Marscar and MENO data using the diffusion + drift model given in Equation 8.17 are shown in

[1] Thanks to Eric Altshuler for this integral



Figure 8.3: Average Displacement of Marscar as a Function of Time Fitted to a Diffusive Model with Drift

Figures 8.3 and 8.4.

The best fit parameters for the diffusion + drift case are as follows. For Marscar $a = 3.27$ ($D = 2.68\text{cm}^2/\text{s}$) and $b = 0.09$ cm/s and for MENO $a = 1.86$ ($D = 0.86\text{cm}^2/\text{s}$) and $b = 0.001$ cm/s. The improvement in the fit performance with the drift term added is approximately 10% of the mean square error in both cases.

8.3 Displacement vs. Energy Model

In Chapter 3 we hypothesized that the average displacement vs. energy consumed is also diffusive in behavior. In Figures 8.5 and 8.6 we show best fits to the data from Marscar and MENO using a purely diffusive model. The best fit parameter for Marscar is $a = 43.15$ ($D = 931$ cm^2/kJ) and for MENO $a = 4.95$ ($D = 6.13$ cm^2/kJ).

As before the fit performance improves with the introduction of a linear term. Figures 8.7 and 8.8 show the resulting best fit curves. The best fit parameters for the



Figure 8.4: Average Displacement of MENO as a Function of Time Fitted to a Diffusive Model with Drift



Figure 8.5: Average Displacement of Marscar as a Function of Energy Fitted to a Diffusive Model



Figure 8.6: Average Displacement of MENO as a Function of Energy Fitted to a Diffusive Model

diffusion + drift case are as follows. For Marscar $a = 48.01$ ($D = 576$ cm^2/kJ) and $b = -1.13$ cm/kJ and for MENO $a = 5.78$ ($D = 8.34$ cm^2/kJ) and $b = -0.03$ cm/kJ.

8.4 Summary

In Chapter 3 we hypothesized that the motion of the legged and wheeled robots under the control of the navigation algorithm could be modeled by a diffusion equation. In this Chapter we have shown best fit solutions of a simple diffusive model to the data obtained from the trials in the MarsBox in Mars Nominal terrain. The results show that when a drift term is added to the model the resulting fits are better than the purely diffusive model.

These fits are supportive evidence that the behavior of both robots can be modeled as a diffusive process with a drift term. A likely interpretation is that the navigation process causes the drift term since without goal seeking behavior we would essentially have a drift term which is a random walk. Future research could use models such as the ones described in this Chapter to measure (statistically) the



Figure 8.7: Average Displacement of Marscar as a Function of Energy Fitted to a Diffusive Model with Drift



Figure 8.8: Average Displacement of MENO as a Function of Energy Fitted to a Diffusive Model with Drift

efficacy of different navigation algorithms by the extent of the drift term they impose on the robot motion.

Chapter 9

Conclusion

We conclude this dissertation with a summary of the major contributions and a short discussion of possible extensions to the present work.

9.1 Summary

This dissertation has primarily contributed to the discipline of mobile robot design evaluation and improvement. Using examples from real applications a foundation for the study of the evaluation process has been laid. Eventual systematization, it is hoped, will lead to universally agreed upon metrics for robot evaluation - this work is a precursor to them. The emphasis of this work is on statistical, multiple criteria based, mission oriented evaluation techniques.

As a focus a particular problem in robot evaluation was studied in this work namely the evaluation of mobile robots designed for Mars exploration. The task used as an example was navigation to a designated goal. The task is typical of what an actual deployed system would execute. In the context of this task, cost functions based on time and energy efficiency were proposed. The functions were evaluated on the systems built in the lab as well as on dynamic simulations of the systems. Excellent agreement was obtained between the two. The simulations were then used to test other designs in the 'neighborhood' of the original designs to measure the

effects of small parameter changes on the evaluation functions. The major research contributions of this work are as follows:

1. A set of functions denoted $\mathcal{F} = \{\tau, \eta\}$ has been found which allow classification of the robot design space. τ is a measure of the time efficiency of a design and η is a measure of its energy efficiency.

2. The proposed functions τ and η have been evaluated on select members of the design space; both in experiment and simulation.

3. A technique using local linearization has been developed to extrapolate to other (untested) members of the design space.

4. A diffusion based model of the reactive navigation strategy employed in the experimental work is exhibited.

As discussed at the end of Chapter 6, the sensitivity studies and the local linearization technique provide avenues for general design optimization applications. In addition to the above contributions this study resulted in several empirical findings which are significant to the Mars mission in particular. In summary those findings are:

1. A methodology for evaluating the comparative effectiveness of Mars locomotion vehicles has been developed

   (a) The methodology has been applied to both legged and wheeled robots in our lab

   (b) The methodology can be applied to a wide class of other vehicles (e.g. tracked, leg/wheel hybrid etc.)

2. For the class of vehicles considered in this study, on a rocky Mars-like terrain with a sparse rock population, wheeled vehicles offer advantages in speed and

energy consumption. In the denser Viking II terrain, legged vehicles lead to better energy figures of merit.

3. Amongst robots that use obstacle avoidance as their main strategy smaller robots have increased mobility in cluttered terrain

9.2 Future Research

The main drawback of the present work is the tedious nature of evaluating the proposed cost functions with physical hardware. In the author's opinion this is inevitable in a thorough evaluation study. The empirical nature of the results implies that a complete exploration of the design space can only be achieved by testing other vehicles with the proposed methodology and populating the tradeoff space with more points. Future enhancements to this work should involve a variety of other benchmarks such as stability, robustness, suitability for longer traverses, degree of autonomy and so on.

Specific future directions for research include:

1. Application of this methodology to other robots
2. Accommodate other criteria in evaluation
3. Address single point failures
4. Measure improvements due to better navigation

Bibliography

Bares, J. & Whittaker, W. (1993), 'Configuration of autonomous walkers for extreme terrain', *International Journal of Robotics Research* **12**(6), 535–559.

Barraquand, J. & Latombe, J. C. (1990), A Monte-Carlo algorithm for path planning with many degrees of freedom, *in* '*Proc. 1990 IEEE Int. Conf. on Robotics and Automation*', pp. 1712–1717.

Bradley, J. V. (1968), *Distribution-Free Statistical Tests*, Prentice-Hall Inc.

Broadbent, S. R. & Kendall, D. G. (1953), 'The random walk of trichostrongylus retortaeformis', *Biometrics* **9**, 460–466.

Brooks, R. A. (1986), 'A robust layered control system for a mobile robot', *IEEE Transactions on Robotics and Automation* **RA-2**(1), 14–33.

Brooks, R. A. (1989), 'A robot that walks: Emergent behaviors from a carefully evolved network', *Neural Computation* **1**(2), 365–382.

Canny, J. (1988), *The Complexity of Robot Motion Planning*, The MIT Press, Cambridge, MA.

Canny, J., Donald, B. R., Reif, J. & Xavier, P. (1988), On the complexity of kinodynamic planning, Technical Report 88-929, Cornell University.

Chankong, V. & Haimes, Y. Y. (1983), *Multiobjective Decision Making*, North-Holland Series in Systems Sciences and Engineering, North-Holland.

Cheng, F. & Orin, D. E. (1991*a*), 'Efficient formulation of the force distribution equations for simple multiple-chain robotic mechanisms', *IEEE Transactions on Systems, Man and Cybernetics* **21**(1), 25–32.

Cheng, F. & Orin, D. E. (1991*b*), 'Optimal force distribution in multiple-chain robotic systems', *IEEE Transactions on Systems, Man and Cybernetics* **21**(1), 13–24.

Cherif, M. & Laugier, C. (1994), Dealing with vehicle/terrain interactions when planning the motions of a rover, *in* '*Proc. 1994 IEEE Int. Conf. on Intelligent Robots and Systems*', pp. 2050–2056.

Cherif, M., Laugier, C., Milesi-Bellier, C. & Faverjon, B. (1994), Planning the motions of an all-terrain vehicle by using geometric and physical models, *in* '*Proc. 1994 IEEE Int. Conf. on Robotics and Automation*', pp. 2050–2056.

Cohon, J. L. & Marks, D. H. (1974), Multiobjective analysis in water resource planning, *in* R. de Neufville & D. H. Marks, eds, 'Systems Planning and Design', Civil Engineering and Engineering Mechanics, Prentice-Hall, pp. 304–321.

Daniel, W. W. (1978), *Applied Nonparametric Statistics*, Houghton Mifflin Company.

Dantzig, G. B. (1963), *Linear Programming and Extensions*, Princeton University Press.

Daubechies, I. (1992), *Ten Lectures on Wavelets*, Society for Industrial and Applied Mathematics.

de Santos, P. G. & Jimenez, M. A. (1995), 'Generation of discontinuous gaits for quadruped walking vehicles', *Journal of Robotic Systems* **12**(2), 599–611.

Dickmanns, E. & Zapp, A. (1987), Autonomous high speed road vehicle guidance by computer vision, *in* 'Automatic Control World Congress 1987, Selected paper from 10th triennial Congress of IFAC', Pergammon Press, pp. 221–226.

Dijkstra, E. (n.d.), 'A note on two problems in connection with graphs', *Numerische Mathematik* **1**, 269–271.

Eschenauer, H. A., Koski, J. & Osyczka, A. (1990), Multicriteria optimization - fundamentals and motivation, *in* H. Eschenauer, J. Koski & A. Osyczka, eds, 'Multicriteria Design Optimization', Springer-Verlag, pp. 1–29.

Facet, T. B. (1970), 'A solution to the multiple objective linear programming problem', MIT Monograph.

Featherstone, R. (1987), *Robot Dynamics Algorithms*, Kluwer Academic Publishers.

Ferrell, C. (1995), 'Global behavior via cooperative local control', *Autonomous Robots* **2**(2), 105–125.

Gat, E. (1994), Navigation templates: Enhancements, extensions, and experiments, *in* '*Proc. 1994 IEEE Int. Conf. on Robotics and Automation*', pp. 541–547.

Gat, E. (1995), 'Towards principled experimental study of autonomous mobile robots', *Autonomous Robots* **2**(3), 179–189.

Gat, E., Behar, A., Desai, R., Ivlev, R., Loch, J. & Miller, D. (1994), Behavior control for robotic exploration of planetary surfaces, *in* '*Proc. 1994 IEEE Int. Conf. on Robotics and Automation*', pp. 567–571.

Gat, E., Desai, R., Ivlev, R., Loch, J. & Miller, D. (1994), 'Behaviour control for robotics exploration of planetary surfaces', *IEEE Transactions on Robotics and Automation* **10**(4), 490–503.

Han, M. & Rhee, S. (1994), 'Navigation control for a mobile robot', *Journal of Robotics Systems* **11**(3), 169–179.

Helmke, U. & Moore, J. B. (1994), *Optimization and Dynamical Systems*, Springer Verlag.

Hirose, S. (1984), 'A study of design and control of a quadruped walking vehicle', *International Journal of Robotics Research* **3**(2), 113–133.

Hirose, S. & Kunieda, O. (1991), 'Generalized standard foot trajectory for a quadruped walking vehicle', *The International Journal of Robotics Research* **10**(1), 3–12.

Hirose, S., Kikuchi, H. & Umetani, Y. (1986), 'The standard circular gait of a quadruped walking vehicle', *Advanced Robotics* **1**(2), 143–164.

Hodgins, J. K. (1991), Biped gait transitions, *in* '*Proc. 1991 IEEE Int. Conf. on Robotics and Automation*', pp. 2092–2097.

Hodgins, J. K. & Raibert, M. H. (1990), 'Biped gymnastics', *The International Journal of Robotics Research* **9**(2), 115–132.

Hollerbach, J. (1983), *Robot Motion*, MIT Press, chapter A Recursive Lagrangian Formulation of Manipulator Dynamics and a Comparitive Study of Dynamics Formulation Complexity.

Hsu, P., Li, Z. & Sastry, S. (1988), On grasping and coordinated manipulation by a multifingered robot hand, *in* '*Proc. 1988 IEEE Int. Conf. on Robotics and Automation*', pp. 991–998.

Hwang, Y. K. & Ahuja, N. (1992), 'Gross motion planning - a survey', *ACM Computing Surveys* **24**(3), 219–291.

Jimenez, S., Luciani, A. & Laugier, C. (1993), Predicting the dynamic behaviour of a planetary vehicle using physical modeling, *in* '*Proc. 1993 IEEE/RSJ Int. Conf. on Intelligent Robots and Systems*', pp. 345–351.

Karmarkar, N. (1984), 'A new polynomial time algorithm for linear programming', *Combinatorica* **4**, 373–395.

Keeney, R. & Raiffa, H. (1993), *Decisions with Multiple Objectives: Preferences and Value Tradeoffs*, Cambridge University Press.

Kerr, J. & Roth, B. (1986*a*), 'Analysis of multifingered hands', *International Journal of Robotics Research* **4**(4), 3–17.

Kerr, J. & Roth, B. (1986*b*), Special grasping configurations with dexterous hands, *in* '*Proc. 1986 IEEE Int. Conf. on Robotics and Automation*', pp. 1361–1367.

Koditscheck, J. (1989), *Robotics Review*, MIT Press, Cambridge, MA, chapter Robot Planning and Control via Potential Functions.

Koenig, P. (1993), A Simulation of Horse and Rider, PhD thesis, University of Southern California.

Krotkov, E. & Hoffman, R. (1994), 'Terrain mapping for a walking planetary rover', *IEEE Transactions on Robotics and Automation* **10**(6), 728–739.

Langer, D., Rosenblatt, J. K. & Hebert, M. (1994), 'A behavior-based system for off-road navigation', *IEEE Transactions on Robotics and Automation* **10**(6), 776–782.

Levitt, T. S. & Lawton, D. T. (1990), 'Qualitative navigation for mobile robots', *Artificial Intelligence* **44**, 305–360.

Lietzau, K. R. (1993), Mars micro rover performance measurement and testing, Master's thesis, Massachusetts Institute of Technology, Department of Aeronautics and Astronautics.

Lily, K. W. (1993), *Efficient Dynamic Simulation of Robotic Mechanisms*, Kluwer Academic Publishers.

Lozano-Perez, T. (1990), Spatial planning - a configuration space approach, *in* G. T. W. I. J. Cox, ed., 'Autonomous Robot Vehicles', Springer-Verlag, pp. 259–271.

Mahalingam, S. & Whittaker, W. L. (1989), Terrain adaptive gaits for walkers with completely overlapping leg workspaces, *in* 'Proc. Robots 13'.

Manko, D. (1992), *A General Model of Legged Locomotion on Natural Terrain*, Kluwer Academic Publishers.

Matthies, L., Gat, E., Harrison, R., Wilcox, B., Volpe, R. & Litwin, T. (1995), 'Mars microrover navigation: Performance evaluation and enhancement', *Autonomous Robots* **2**(4), 291–311.

McGhee, R. B. & Frank, A. A. (1968), 'On the stability properties of quadruped creeping gaits', *Mathematical Biosciences* **3**(3/4), 331–351.

Messuri, D. A. & Klein, C. A. (1985), 'Automatic body regulation for maintaining stability of a legged vehicle during rough terrain locomotion', *IEEE Journal of Robotics and Automation* **RA-1**(3), 132–141.

Milesi-Bellier, C., Laugier, C. & Faverjon, B. (1993), A kinematic simulator for motion planning of a mobile robot on a terrain, *in* '*Proc. 1993 IEEE/RSJ Int. Conf. on Intelligent Robots and Systems*', pp. 339–344.

Moore, H. J. & Jakosky, B. M. (1989), 'Viking landing sites, remote-sensing observations and physical properties of Martian surface materials', *Icarus* **81**, 164–184.

Nagy, P., Desa, S. & Whittaker, W. L. (1994), 'Energy-based stability measures for reliable locomotion of statically stable walkers: Theory and application', *The International Journal of Robotics Research* **13**(3), 272–287.

Okubo, A. (1980), *Diffusion and Ecological Problems: Mathematical Models*, Vol. 10 of *Biomathematics*, Springer-Verlag.

Orin, D. (1979), 'Kinematic and kinetic analysis of open-chain linkages utilizing Newton-Euler methods', *Mathematical Biosciences* **43**, 107–130.

Pareto, V. (1971), *Manual of Political Economy: Translation of the French Edition (1927)*, The McMillan Press Ltd.

Pielou, E. C. (1969), *An Introduction to Mathematical Ecology*, Wiley Interscience.

Pomerleau, D. (1992), Neural Network Perception for Mobile Robot Guidance, PhD thesis, Carnegie-Mellon University.

Raibert, M. H. (1986), *Legged Robots that Balance*, The MIT Press, Cambridge. Massachusetts.

Raibert, M. H. & Wimberly, F. C. (1984), 'Tabular control of balance in a dynamic legged system', *IEEE Transactions on Systems Man and Cybernetics* **14**(2), 334–339.

Raibert, M. H., Jr., H. B. B. & Chepponis, M. (1984), 'Experiments in balance with a 3d one-legged hopping machine', *The International Journal of Robotics Research* **3**(2), 75–92.

Raiffa, H. (1968), *Decision Analysis*, Addison-Wesley.

Risken, H. (1984), *The Fokker-Planck Equation: Methods of Solution and Applications*, Springer-Verlag.

Roston, G. P. & Krotkov, E. P. (1991), Dead reckoning navigation for walking robots, Technical Report CMU-RI-TR-91-27, Carnegie Mellon University.

Simmons, R. (1994), 'Structured control for autonomous robots', *IEEE Transactions on Robotics and Automation* **10**(1), 34–43.

Skellam, J. G. (1951), 'Random dispersal in theoretical populations', *Biometrika* **38**, 196–218.

Song, S. & Waldron, K. J. (1989), *Machines that Walk: The Adaptive Suspension Vehicle*, The MIT Press, Cambridge, Massachusetts.

Sukhatme, G. S. & Bekey, G. A. (1996), Multicriteria evaluation of a planetary rover, *in* '*Proc. Workshop on Planetary Rover Technology and Systems, 1996 IEEE Int. Conf. on Robotics and Automation*'.

Tsukagoshi, H., Hirose, S. & Yoneda, K. (1996), Maneuvering operations of the quadruped walking robot on the slope, *in* '*Proc. 1996 IEEE/RSJ Int. Conf. on Intelligent Robots and Systems*', pp. 863–869.

Vijaykumar, R. (1987), Motion Planning for Legged Locomotion Systems on Uneven Terrain, PhD thesis, The Ohio State University.

Volpe, R., Balaram, J., Ohm, T. & Ivlev, R. (1996), The rocky 7 mars rover prototype, *in* '*Workshop on Planetary Rover Technology and Systems, 1996 IEEE International Conference on Robotics and Automation*'.

Wilcox, B. (1991), 'Mobility characteristic curve', Jet Propulsion Labs, IOM 3472-91-019.

Zhang, C. D. & Song, S. M. (1989), 'Gaits and geometry of a walking chair for the disabled', *Journal of Terramechanics* **26**(3/4), 211–233.